

15-165-20340-0000

KANSAS

Form CP-3  
Rev. 6-4-68

12

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENCY'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 21 1977  
CONSERVATION DIVISION  
Wichita, Kansas  
(for this well)

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - -

Operator's Full Name Frontier Oil Co.

Complete Address 1720 Kansas State Bank Bldg., Wichita, Kansas 67202

Lease Name Allen "C" Well No. 1

Location NE NE SE Sec. 11 Twp. 17 Rge. (E) (W) 17

County Rush Total Depth 3676'

Abandoned Oil Well        Gas Well XX Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Co. Tools by Allied Cementing Co.

Address Russell, Kansas License No.       

Operation Completed: Hour 9 A Day 19 Month 12 Year 1977

The above well was plugged as follows:

Total Depth 3676' 8 5/8 csg set 208' cwc 150 sk.

4 1/2 csg set 3233' cw 150 sk cem. Perf. (3103'-3110')

4 1/2 csg DV tool set 1230' cwc 450 sk. No pipe recovered.

Allied Cementing Co. mixed & pumped down 4 1/2 csg with 35 sk cem. W/300 lbs hulls -

displaced with 20 sk gel & water & capped with cementing plug & 45 sk cem. & shutin.

SIP 1800 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey  
Well Plugging Supervisor

DATE 12-21-77  
6429.W