

R

Form CP-3

Rev. 6-1-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 28 1978
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 135 - 21,429 0000 (of this well)

Operator's Full Name Icer Addis

Complete Address P. O. Drawer 8038, Wichita, Kansas

Lease Name Baer Well No. 1

Location C SW NW Sec. 33 Twp. 17 Rge. (E) (W) 23

County Ness Total Depth 4384'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Strata Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 6:30 P Day 25 Month 2 Year 1978

The above well was plugged as follows:

RTD 4384' 8 5/8 csg set 300' cwc 200 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 720' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

2-28-78
6837-W

Signed: Leo Massey
Well Plugging Supervisor