

15.135.20482.0000

Form CP-3
Rev. 6-4-68

KANSAS

Y STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 10 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Pickrell Drilling Company
Complete Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202
Lease Name Anspaugh "A" Well No. 1
Location C NW NE Sec. 33 Twp. 17 Rge. (E) (W) 23
County Ness Total Depth 4389'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Russ Casing Pulling Co.
Address Box 1082 Great Bend, Kansas 67530 License No. 623
Operation Completed: Hour 12 N Day 6 Month 1 Year 1972

The above well was plugged as follows:

Total Depth 4389' 8 5/8 csg set at 233' cwc 140 sk.
5 1/2 csg set at 4379' cw 125 sk cmt.
Filled 5 1/2 csg W/sd (4350-4389) Dumped 5 sk cmt W/dump bailer. (4315-4350)
Cutoff and recovered 2850' of 5 1/2 csg.
Pumped down 8 5/8 csg with 20 sk gel & water W/200 lbs hulls -60 sk 50-50 poz cmt
W/6% total gel -5 sk gel & water -released plug and pumped 60 sk 50-50 poz cmt W/6%
total gel. PSI 500.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey
Well Plugging Supervisor

DATE 1-13-72
INV. NO. 4990-W