

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-20327-0000

LEASE NAME Clark

WELL NUMBER #2

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

660 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 13 TWP. 19 RGE. 30 (E) or (W)

EASE OPERATOR Murfin Drilling Company

DDRESS 250 N. Water, Suite 300, Wichita, KS 67202 COUNTY Lane

PHONE# (316) 267-3241 OPERATORS LICENSE NO. 6033

Date Well Completed 8/21/78

Character of Well oil

Plugging Commenced 9/10/90

Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 9/12/90

The plugging proposal was approved on 9/11/90 (date)

By Steve Durrant (KCC District Agent's Name).

Is ACO-1 filled? No If not, is well log attached? Yes

Producing Formation Altamont/Pawnee Depth to Top 4402 Bottom 4480 T.D. 4675

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	330	w/250 sx
				5 1/2	4672	w/1400 gal Latex
				9/12/90		Rec. 730' of 5 1/2"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from feet to feet each set.

Filled 5 1/2" csg w/sand from TD to 4340'. Placed 5 sx cmt on top of sand. Perf csg @ 1300'. Pumped dwn csg 100 sx 60/40 Poz w/6% gel displacing 50 sx cmt out of perms and 50 sx cmt inside csg @ 900'. Max press 400 psig, STP 300 psig. Shot csg off @ 730'. Pumped 5 sx gel and 50 sx 60/40 Poz w/6% gel @ 648' and displaced cmt to 570'. Laid dwn csg to 361' (over)
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Murfin Drilling Company License No. 6033

Address 250 N. Water, Suite 300 Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company

STATE OF KS COUNTY OF SG, ss.

Larry M. Jack, Production Manager

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) By: Larry M. Jack

Wichita, KS

(Address)

OCT 11 1990
10-11-90

SUBSCRIBED AND SWORN TO before me this 10 day of October, 19 90

My Commission Expires: 2/6/94

Kerran Redington
Notary Public

