

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

15-101-20335-0000

API NUMBER compl 9/78

LEASE NAME Hess

WELL NUMBER #1

4620 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 23 TWP. 19 SRGE. 30 (E) or (W)

COUNTY Lane

Date Well Completed 9/21/78

Plugging Commenced 9/13/90

Plugging Completed 12/11/90

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Murfin Drilling Company

ADDRESS 250 N. Market, Suite 300, Wichita, KS 67202

PHONE#(316) 267-3241 OPERATORS LICENSE NO. 6033

Character of Well Oil

Oil, Gas, D&A, SWD, Input, Water Supply Well

The plugging proposal was approved on 7/17/90 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation Marmaton Depth to Top 4406 Bottom 4410 T.D. 4680

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	326'	w/250 sx
				5 1/2	4660	w/1400 gal Latex
	12/18/84 - Sq'd @	1960-96	w/200	sx		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from feet to feet each set.  
9/13/90 - Dumped 6000# of sand w/55 BSW dwn csg. Bridged off @ 2484'. Unable to sand pump.  
12/11/90 - Tagged btm plug @ 2472'. Perf @ 1400-01 w/4 spf. Pumped dwn 5 1/2" csg w/200 sx  
60/40 Poz w/6% gel. Max press 1000 psig; SIP 500 psig. Pumped dwn 5 1/2" & 8 5/8" annulus w/40 sx  
of same cmt. Circ into cellar. Approved by Dan Goodrow w/KCC in Dodge City, KS.  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Murfin Drilling Company License No. 6033

Address 250 N. Water, Suite 300 Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company

STATE OF Kansas COUNTY OF Sedgwick, ss.

Larry M. Jack, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Larry M. Jack

(Address) Larry M. Jack, Production Manager  
 Wichita, KS

SUBSCRIBED AND SWORN TO before me this 26 day of Dec, 19 90

Kerran Redington  
 Notary Public



Commission Expires: 2/6/94 Kerran Redington

