

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME Dueser A

WELL NUMBER 1

550 Ft. from N Section Line

1770 Ft. from W Section Line

SEC. 4 TWP. 17S RGE. 29W (E) or (W)

COUNTY Lane

Date Well Completed _____

Plugging Commenced 10/29/98

Plugging Completed 12/2/98

EASE OPERATOR Whitetail Crude, Inc

ADDRESS P O Box 544, Ness City, KS 67560-0544

PHONE(S) () 785-798-3641 OPERATORS LICENSE NO. 31627

Character of Well Oil

Oil, Gas, D&A, SWD, Input, Water Supply Well

The plugging proposal was approved on _____ (date)

by Kevin Strube (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Kansas City/Marmington Depth to Top 4520 Bottom 4553 T.D. 4649

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Kansas City		0	364	8 5/8	364	-0-
Marmington		0	4649	4 1/2	4649	766' pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug is used, state the character of same and depth placed, from _____ feet to _____ feet each set
Mix 25 sks of 60/40 6% gel + 300# of hulls & displaced to 3507'. Came back on 12/2/98 and perforated @ 1200'. Mixed 50 sks + 50# of hulls & displaced to 900'. Shot the casing off @ 766' and mixed 40 sks & displaced to 600'. Pulled pipe up to 360' and pumped a 40 sks plug. Pulled pipe and topped off with 20 sks.

Name of Plugging Contractor Allied Cementing Co Inc License No. 12-14-1998

Address P O Box 31, Russell, KS 67665


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Whitetail Crude, Inc

STATE OF Kansas COUNTY OF Ness, ss.

Mike J. Fritzler, President of Whitetail Crude, Inc (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed there and the same are true and correct, so help me God.

(Signature) Mike J. Fritzler

(Address) P O Box 544, Ness City, KS 67560-0544



SUBSCRIBED AND SWORN TO before me this 10th day of December, 19 98

Notary Public Debra Kerr

My Commission Expires: 4/20/2001

USE ONLY ONE SIDE OF EACH FORM

Hetro-Log

Radiation Guard Log

15-101-20628-0000

COMPANY DONALD C. SLAWSON
 WELL #1 DUESER 'A'
 FIELD
 COUNTY LANE KANSAS

Location
 Approx 200' SE of C-NW-NE-NW
 Sec. 4 17S 29W
 Permanent Station GL 2816
 Log Measured from KB 6 2813
 Drilling Measured from KB 2810

Date	2-23-82	
Run No.	ONE	
Depth—Driller	4650	
Depth—Logger	4642	
Bot. Log Inter.	4641	
Top Log Inter.	0	
Casing—Driller	8 5/8	* 340
Casing—Logger		
Bit Size	7 7/8	
Type Fluid in Hole	CHEMICAL	
Dens.	Visc.	9.5 60
pH	Fluid Loss	10.0 7.2 ml
Source of Sample	FLOWLINE	
R ₁₀₀ @ Meas. Temp.	.7	* 56 °F
R ₅₀ @ Meas. Temp.	.53	* 56 °F
R ₂₅ @ Meas. Temp.	.106	* 56 °F
Source: R ₁₀₀ R ₅₀	CALC	
R ₁₀₀ @ BHT	.32	* 122 °F
Time Since Circ.	2 hrs	
Max. Rec. Temp.	122	
Equip. Location	H-8	
Recorded By	JOHN THAGGARD	
Witnessed By	MR. JEFF STEWART	