

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE NAME Dueser A

WELL NUMBER 2

1000 Ft. from N Section Line

900 Ft. from W Section Line

SEC. 4 TWP. 17S RGE. 29W (X) or (W)

COUNTY Lane

Date Well Completed \_\_\_\_\_

Plugging Commenced 10/28/98

Plugging Completed 10/28/98

EASE OPERATOR Whitetail Crude, Inc

ADDRESS P O Box 544, Ness City, KS 67560-0544

PHONE ( ) 785-798-3641 OPERATORS LICENSE NO. 31627

Character of Well Oil

Oil, Gas, O&A, SWD, Input, Water Supply Well

The plugging proposal was approved on \_\_\_\_\_ (date)

by Kevin Strube (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ if not, is well log attached? \_\_\_\_\_

Producing Formation Kansas City/Lansing Depth to Top 4330 Bottom 4334 T.D. 4619

show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	341	8 5/8	341	---
		0	4619	4 1/2	4619	694 pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug was used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set. Sanded the bottom off & spotted 4 sks of cement with a dump bailer. Perforated well @ 1150' & mixed 60 sks of 60/40 6% gel & pumped down. Well did not load, mixed 40 sks + 200# of hulls & displaced to 1100'. Well still on a vacuum. Wait 2 hrs, mix 80 sks with 500# hulls & displaced to 780' & shut in @ 400 PSI. Shot the pipe off @ 694' & pumped a 30 sk plug @ 600'. Pumped 40 sks @ 360 pulled pipe and topped off with 40 sks.

11-04-1998

Name of Plugging Contractor Allied Cementing Co Inc License No. \_\_\_\_\_

Address P O Box 31, Russell, KS 67665


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Whitetail Crude, Inc

STATE OF Kansas COUNTY OF Ness, ss.

Mike J. Fritzler, President of Whitetail Crude, Inc (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Mike J. Fritzler

(Address) P O Box 544, Ness City, KS 67560-0544



SUBSCRIBED AND SWORN TO before me this 10th day of December, 19 98

Debra Kerr  
Notary Public Debra Kerr

My Commission Expires: 4/20/2001

USE ONLY ONE SIDE OF EACH FORM