

API NUMBER 1510120986 -0000

LEASE NAME Munsell

WELL NUMBER 2

3630 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 3 TWP. 17 RGE. 29 (E) or (W)

COUNTY Lane County

Date Well Completed 7-30-84

Plugging Commenced 7-11-95

Plugging Completed 7-11-95

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR A. L. Abercrombie, Inc.

ADDRESS Rt. #1 Box 56 Great Bend, Ks. 67530

PHONE#(316) 793-8186 OPERATORS LICENSE NO. 5393

Character of Well Oil

(Oil), Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-8-95 (date)

by David P. Williams Prod. Supr. (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached?

Producing Formation Marmaton Depth to Top 4316 Bottom 4318 T.D. 4600

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	335'	None
Marmaton	Oil - water	4316	18	4 1/2	4590'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set  
Plug as follows - pump 600# hulls, 200 sacks 65/35 poz mix 8% Gel down 4 1/2" casing  
Shut in pressure 400# Mix & pump 2 sacks 65/35 poz 8% Gel down surface casing  
150# standing. Steve Middleton KCC Pluggger present

Name of Plugging Contractor A. L. Abercrombie, Inc. License No. 5393

Address Rt. #1 Box 56 Great Bend, Ks. 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: A. L. Abercrombie, Inc.


STATE OF Kansas COUNTY OF Barton, ss.

E. L. Abercrombie (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) E L Abercrombie

(Address) Rt. #1 Box 56 Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 20th day of July, 19 95



Susan M. Evers  
Notary Public

My Commission Expires: 7-29-96

USE ONLY ONE SIDE OF EACH FORM