


WELL PLUGGING RECORD

Get All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas



Locate well correctly on above Section Plat

Saline County, Sec. 33 Twp. 16S Rge. 1W (E) (W)  
Location as "NE/CNW/SW" or footage from lines CSL SW/4  
Lease Owner F. S. Williams  
Lease Name Stein "A" Well No. 5  
Office Address 202 Maltby Bldg. - McPherson, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed 6/19/54 19  
Application for plugging filed 6/25/55 19  
Application for plugging approved 7/16/55 19  
Plugging commenced March 7 19 56  
Plugging completed March 9 19 56  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 2622 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Chat 2612 - 21 1/2</u>	<u>B BOPD</u>			<u>8-5/8"</u>	<u>120'</u>	<u>None</u>
<u>Perf KC</u>	<u>No Results</u>			<u>5-1/2"</u>	<u>2611'</u>	<u>1782'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled the hole with sand from 2622' to 2600' and ran 6 sacks of cement. Mudded the hole to 125', set a 10' rock bridge and ran 15 sacks of cement. Mudded the hole to 25', set a 10' rock bridge and ran 5 sacks of cement on top. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.  
Address Chase, Kansas

STATE OF Kansas, COUNTY OF McPherson, ss.  
F. S. Williams (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. S. Williams  
Box 746 McPherson Kansas (Address)

SUBSCRIBED AND SWORN to before me this 15 day of May, 1956

My commission expires 9-14-1958

RECEIVED Notary Public.  
STATE CORPORATION COMMISSION  
MAR 16 1956  
CONSERVATION DIVISION  
Wichita, Kansas

**PLUGGING**  
FILE SEC 33 T 16 R 1W  
BOOK PAGE 123 LINE 37

ROTARY DRILLER'S LOG

15-169-00908-0000

F. S. Williams  
Maltby Building  
McPherson, Kansas

Est. Elevation: 1285 K.B.

8-5/8" x 5 1/2" Head 6.30'  
below K. B.

Stein #5

SE SW SW  
Sec. 33-16-1W  
Saline County, Kansas

Casing Record:

3-5/8" @ 120' w/35 sks.  
Ash Grove cement & 100% cc.

Well Commenced: 6-13-54  
Well Completed: 6-20-54

5-1/2" 2611' w/150 sks.  
Pozmix cement. Cemented 2'  
off bottom.

Contractor: E. K. Carey, Contractor, Rig #2, Box 620, McPherson, Kansas  
Geologist: F. S. Williams, Maltby Building, McPherson, Kansas

Figures Indicate Bottom of Formation K. B.

Base and cellar	7
Sand and shale	15
Sand	30
Shale	65
Shale and shells	100
Shale	114
Lime	850
Shale and lime	1060
Shale and lime	1250
Lime and shale	1540
Lime	1790
Shale and lime	1990
Lime	2145
Lime and shale	2240
Lime	2330
Shale and lime	2430
Lime and shale	2560
Shale and lime	2608
Lime (Miss)	2613 TD

Geologist Tops:

Top Kansas City 2015  
Chat 2608

Rotary Total Depth 2613

*2015  
Catcher Sells  
2613 - 2620 1/2 Lim & Chat  
AFW 2620 - 21 1/2  
DPA.*

This is to certify that the above information is to the best of my knowledge true and correct.

SUBSCRIBED AND SWORN to before me this 21st day of June, 1954.

E. K. CAREY CONTRACTOR

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 2 - 1954  
REGISTRATION DIVISION

BY Herbert Rhoton  
Herbert Rhoton, Superintendent

[Signature]  
NP

My Commission Expires: November 13, 1956

PLUGGING  
SEC 34-16-1W  
BOX 2123-32