

15-169-00664-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Exact Address
Mail or Delivery Report to
Conservation Division
State Corporation Commission
500 McKay Building
Wichita, Kansas

Saline County, Sec. 22 Twp. 16 Rge. 1 (#E) (W)

Location as "NE/CNWSWA" or footage from lines NE SW SW

Lease Owner George Hess

Lease Name Mayer Well No. 1

Office Address 505 N. Charles

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed November 6 19 58

Application for plugging filed "-Oral 19 58

Application for plugging approved " 19 58

Plugging commenced " 19 58

Plugging completed " 19 58

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes--oral

Name of Conservation Agent who supervised plugging of this well Gilbert Tomen, Holyrood, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2673 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	166	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole full heavy mud to 166 ft.
Drove wooden plug to 166 ft. and dumped in 20 sacks cement,
finished filling hole full heavy mud to within 35 ft of cellar
and dumped in 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Mallard Drilling Company

Address 419 Union National Bldg.

STATE OF Kansas COUNTY OF Sedgwick, ss.

C. C. Nelson, partner Mallard Drg. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. C. Nelson

(Address)

Subscribed and Sworn to before me this 11th day of November, 1958

Edward U. Sauer

My commission expires March 12, 1962

RECEIVED
STATE CORPORATION COMMISSION
Notary Public.

PLUGGING
FILE SEC. 22 T. 16 R. 1W
BOOK PAGE 144 LINE 37

NOV 12 1958

VISION

COMPANY: George Hess
 CONTRACTOR: Mallard Drilling Company
 FARM: Mayer #1
 LOCATION: NE SE SW Sec. 22-16-1W
 Saline County, Kansas
 COMMENCED: October 31, 1958
 COMPLETED: November 6, 1958

0	to	40	Sand
40	to	166	Shale and shells
166	to	240	Lime
240	to	855	Lime
855	to	1195	Shale
1195	to	1555	Shale and shells
1555	to	1885	Lime
1885	to	2001	Shale
2001	to	2080	Lime
2080	to	2420	Lime
2420	to	2550	Lime and shale
2550	to	2667 $\frac{1}{2}$	Lime and shale
2667 $\frac{1}{2}$	to	2669	Mississippi
2669	to	2675	Mississippi
		2675	T.D.

Set 166 ft of 8 5/8" surface pipe. Cemented with 105 sacks cement.
 Elevation -- 1334 D.F.
 TOPS: Mississippi 2667 $\frac{1}{2}$
 D.S.T. at 2675. Recovered 75 ft. water.

Measurements taken from R.D.B. R.D.B. 5 $\frac{1}{2}$ ' from ground level.
 DRY, ABANDONED AND PLUGGED.

C E R T I F I C A T E

I, C. C. Nelson, do hereby certify that the above and foregoing is a true and correct copy of log of the Mayer #1, Saline County, Kansas, as reflected by files of the Mallard Drilling Company.

C. C. Nelson

Subscribed and sworn to before me a Notary Public, within and for Sedgwick County, Kansas, this 11th day of November 1958.

My commission expires March 12, 1962

RECEIVED
 STATE COMMISSIONER

NOV 12 1958

CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC. 2216 R1W
 BOOK PAGE 144 LINE 37