


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Saline County. Sec. 32 Twp. 16 Rge. 1 (E) W (W)

Location as "NE/CNWxSWx" or footage from lines. C S/2 NW SE
Lease Owner George R. Hess & Sons
Lease Name Van Meter "B" Well No. 2
Office Address 505 N. Charles, McPherson, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil well
Date well completed 5-2-63 19
Application for plugging filed 12-4-69 19
Application for plugging approved 12-7-69 19
Plugging commenced 12-17-69 19
Plugging completed 12-20-69 19
Reason for abandonment of well or producing formation depleted



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 134' | none |
| | | | | 5 1/2" | 2650' | 2181.38' |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled bottom from 2659' to 2625' with sand, mixed and dumped 5 sacks of cement.

Set a 10' rock bridge from 160' to 150', dumped 20 sacks of cement, mud hole to 40', added 10' of rock and 10 sacks of cement to surface.

RECEIVED
STATE CORPORATION COMMISSION
JAN 5 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Flint Engineering and Construction Co.
Address 2375 W. Central, El Dorado, Kansas

STATE OF Kansas COUNTY OF Butler, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Richard C. Houseman


Subscribed AND SWORN to before me this 30th day of December, 19 69

(Address) James J. Davis

Notary Public.

9-19-70





15-169-19019-0060

Blackstone Drilling, Inc.

P. O. BOX 455 • PHONE CH 1-1250
McPHERSON • KANSAS

May 3, 1963

RECEIVED
STATE CORPORATION COMMISSION
DEC 8 1969
CONSERVATION DIVISION
Wichita, Kansas

COMPANY: GEORGE R. HESS
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: VAN METER # B-2
 LOCATION: C-6/2 NW/4 SE/4, Sec. 32-16-1W,
 Saline County, Kansas
 COMMENCED: April 24, 1963
 COMPLETED: May 2, 1963
 ELEVATION: 1319 K.S.

| | | | |
|------|----|------|--------------|
| 0 | to | 132 | Shale |
| 132 | to | 630 | Line |
| 630 | to | 960 | Line & Shale |
| 960 | to | 1475 | Shale & Line |
| 1475 | to | 1595 | Line & Shale |
| 1595 | to | 1765 | Line |
| 1765 | to | 2043 | Line & Shale |
| 2043 | to | 2375 | Line |
| 2375 | to | 2647 | Line & Shale |
| 2647 | to | 2659 | Mississippi |
| | | 2659 | T. D. |

Cut 12 1/4 in. hole to 132 ft. and run 134 ft. of 3 5/8 in. surface pipe, and set on bottom at 132 ft. with 95 sacks cement and 2 sacks chloride. Plug down at 10:15 A.M. on April 24, 1963. Cut 7 7/8 in. hole to 2659 ft. and run 2668 ft. of 5 1/2 in. O.D. casing and cemented 9 ft. off bottom at 2650 ft. with 35 sacks cement. 1 sack in rathole. Plug down at 12:30 P.M. May 2, 1963.

TOPS: Brown - 1985' Kansas City - 2043' Mississippi - 2648'

Measurements taken from K. S.

Small sho. + order not enough to test. off lower than 2 H lower than no 1 B.

CERTIFICATE

I, H. J. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on the Van Meter # B-2, located on Sec. 32-16-1W, McPherson County, Kansas as reflected by files of the Blackstone Drilling, Inc.

H. J. Plouffe
 H. J. Plouffe, President

Subscribed and sworn to before me a Notary Public, within and for McPherson County, Kansas this 3rd day of May, 1963.

Ruth McVay
 Ruth McVay, Notary Public

My Commission Expires: Dec. 18, 1965