

Hand to ↓

15-169-00960-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Saline County, Sec. 11 Twp. 16 Rge. 4 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE NE NW  
Lease Owner Jones, Shelburne & Farmer, Inc.  
Lease Name Lagerstrom #2 Well No. \_\_\_\_\_  
Office Address Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 10-19-57 19\_\_\_\_  
Plugging completed 10-22-57 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Earl Burkee  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3468 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	206'	none
				5-1/2"	3466'	2932'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked the hole to 3468' and found it open. Filled w/sand to 3455' and ran 6 sacks of cement. Pulled 5 1/2" casing. Mudded the hole to 210' and set a 10' rock bridge to 200' and ran 15 sacks of cement to 155'. Mudded the hole to 25', set a rock bridge and ran 5 sacks of cement to base of collar.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 25 1957  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor West Supply Co., Inc.  
Address Chase, Kansas

STATE OF \_\_\_\_\_ COUNTY OF \_\_\_\_\_, ss.  
\_\_\_\_\_, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John W. Farmer  
(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this \_\_\_\_\_ day of \_\_\_\_\_, 19\_\_\_\_

My commission expires 4-5-1961 \_\_\_\_\_  
James Hall Notary Public.

PLUGGING  
FILE SEC. 11 T. 16 R. 4 W  
BOOK PAGE 54 LINE 4



# Shields


Russell, Kansas

## WELL LOG

15:169-00960-0000

Operator: Jones, Shelburne & Farmer, Inc.  
 Well: Lagerstrom #2  
 Commenced: November 1, 1954  
 Completed: November 25, 1954  
 Contractor: Shields Drilling Co., Inc.

Well Description: N/2 N/2 NW/4  
 Sec. 11, Twp. 16S, Rge. 4W  
 Saline County, Kansas



### CASING RECORD

Size	Run	Pulled
8 5/8"	396'	Cmtd. w/450 sax
5 1/2"	3466'	Cmtd. w/75 sax

Elevation: 1357' RB

Treatment:

Production:

Tops: Maquoketa Dolomite 3466'

.....Figures Indicate Bottom of Formations.....

Surface Clay	30	
Sand	45	
Shale	355	
Anhydrite	380	
Shale & Lime Streaks	480	
Lime & Shale	840	
Lime	990	
Shale	1180	
Shale & Lime	1220	
Shale & Salt	1250	
Shale	1400	
Shale & Lime Streaks	1570	
Lime & Shale	2065	
Shale & Lime	2270	
Lime & Shale	2665	
Shale & Lime Streaks	2715	
Lime & Shale	3050	
Lime	3176	
Lime & Shale	3203	
Lime	3226	
Lime & Shale	3278	
Shale	3466	
Maquoketa Dolomite	3468	RTD

RECEIVED  
 OCT 17 1957  
 CONSERVATION DIVISION  
 STATE OF KANSAS

Notes

PLUGGING  
 FILE SEC. 11 T 16 R 4W  
 BOOK PAGE 54 LINE 12