

WELL PLUGGING RECORD

One of following completely  
filled with cement  
and sealed with  
mud or other plug  
material.

Saline County, Sec. 11 Twp. 16 Rge. 4 (E) W.(W)

Location as "NE/CNW/SW" or footage from lines C NW NW NE

Lease Owner McPherson Operating Co.

Lease Name Ryding Well No. 1

Office Address Box 326, McPherson, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed 7-10 19 53

Application for plugging filed 11-12 19 53

Application for plugging approved 11-13 19 53

Plugging commenced 11-12- 19 53

Plugging completed 11-17 19 53

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	FILLED OUT
cemented with 260 sacks				8 5/8	378	none
" with 50 sacks				5 1/2	3443	2350

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3444 feet to \_\_\_\_\_ feet for each plug set.

Plugged back from 3517 to 3435 with sand. Dumped six sacks cement. Ripped 5 1/2 at 2350'. Filled hole with mud set bridge 195'. Filled with rock back to 180'. Dumped 15 sacks cement. Filled with mud to 15'. Set bridge and capped with 5 sacks cement.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor The McPherson Oil Company  
Address Box 326, McPherson, Kansas

STATE OF Kansas, COUNTY OF McPherson, ss.  
J. S. Cling, operator (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. McPherson Operating Co.

(Signature) J. S. Cling  
Box 326, McPherson, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of November, 19 53

My commission expires 6-29-57

Eddley M. Maloy Notary Public.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 19 1953

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 11 T 16 R 40  
BOOK PAGE 112 LINE 13

McPherson Operating Co., Lease Owner

Section 11-16-4W

Donald T. Ingling, Contractor

Location: G NW NW NE

Commenced: 6-13-53

County: Saline, Kansas

Completed: 7-6-53

Production:

Total Depth: 3444'

Elevation:

Casing: 8 5/8" - 378' (260 sacks cement)  
5 1/2" - 3443' (50 sacks cement)

Figures below indicate bottom formation

285 Shale and shells	2360 Lime
335 Shale and salt	2440 Lime
345 Shale and shells	2474 Lime
366 Shale and shells	2505 Lime
378 Lime	2595 Lime
392 Anhydrite	2635 Lime
420 Lime	2675 Lime and shale
680 Shale and lime	2705 Lime
800 Lime and shale streaks	2740 Lime
825 Shale	2850 Lime
915 Lime	2875 Shale
995 Lime and shale	2942 Shale
1105 Lime and shale	2945 Lime
1175 Shale and lime	2980 Mississippi
1255 Shale and shells	3005 Lime
1455 Shale and shells	3065 Lime
1500 Shale and shells	3096 Lime chirty
1505 Shale and shells	3130 Lime chirty
1630 Shale and shells	3160 Lime
1710 Shale and lime streaks	3180 Lime
1795 Shale and shells	3205 Lime
1855 Lime and shale	3225 Lime
1890 Lime	3250 Shale
1950 Lime and shale	3280 Shale
2005 Broken lime	3443 Top Maquo
2070 Lime	3444 Total Depth
2115 Lime and shale	
2235 Lime and shale	
2311 Lime and shale streaks	
2320 Lime	

**PLUGGING**  
FILE SEC 11 T 16 R 4W  
BOOK PAGE 142 LINE 13

I certify this is a true and correct log of the above mentioned well.

RECEIVED  
STATE CORPORATION COMMISSION  
D. T. Ingling  
NOV 19 1953  
CONSERVATION DIVISION  
Wichita, Kansas

State of Kansas )  
County of Sedgwick ) ss

Subscribed and sworn to before me, a Notary Public in said County and State

My commission expires Feb. 27, 1956

*W. E. Black*  
Notary Public

15.169.00729.0000

WELL LOG - RYDING NO. 1

McPherson Operating Company., Lease Owner

Section 11-16-4W

McPherson Oil Company - Contractor

Location: C NW NW NE

3444 to 3446 Maquo

3446 to 3517 Broken Sand & Lime T. D.

**RECEIVED**  
STATE CORPORATION COMMISSION  
NOV 19 1953  
CONSERVATION DIVISION  
Wichita, Kansas