


Give All Information Completely  
Make Required Affidavit  
Mail Receiver Report to:  
Conservation Division  
State Corporation Commission  
1001 Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Saline County, Sec. 1 Twp. 16 Rge. 4 (E) W (W)  
C E/2 NW NW

NORTH



Locate well correctly on above Section Plat

Location as "NE/CNW%SW%" or footage from lines \_\_\_\_\_  
Lease Owner Krehbiel & Buller  
Lease Name Ryding Well No. 4  
Office Address McPherson, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 8-5-63 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 8-13-63 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3434 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	372'	None
				5-1/2"	3433'	2793'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole, ran sand to 3340' and dumped 5 sacks of cement @ 3340' with dump bailer. Pulled 5 1/2" casing, checked hole to 219', set rock bridge and ran 20 sack\* of cement. Mudded to 30' and capped with 10 sacks of cement

RECEIVED  
STATE CORPORATION COMMISSION

OCT 31 1963

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY  
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss. Noel J. Knight (employee of owner) or ~~(owner or agent)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas

SUBSCRIBED AND SWORN TO before me this 19th day of August, 1963

Melton J. Volin

My commission expires May 20, 1964

Notary Public

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


15/69-00944-0000

Company- PHILLIPS & SANDERSON  
Farm- Ryding No.4

SEC. 1 T. 16 R. 1W  
G E  $\frac{1}{2}$  NW NW

Total Depth. 3436  
Comm. 2-13-53 Comp. 2-26-53  
Shot or Treated.  
Contractor.  
Issued. 12-5-53

County Saline  
KANSAS



CASING:

8 5/8" 372' com. w/325 sx  
5 1/2" 3433' com. s/ 61 sx

Elevation. 1325

Production. 169 BO & 4% wtr

Figures indicate Bottom of Formations.

surface & shale	50
sandy shale	80
shale	165
shale & sholls	195
sandy shale & gyp	255
anhydrite	435
lime	540
red rock	575
shale, lime & shells	795
sandy lime & shale	860
shale & shells	910
sandy lime & shale	1090
sandy lime	1220
shale & sholls	1655
shale & lime strks	1785
lime & shale	2175
lime	2615
lime & shale	2720
lime	2795
lime & shale	2820
shale	2920
shale & limo	2935
shale	2990
limo & shale	3020
chort	3125
lime & chort	3200
lime & shale	3436
Total Depth	

SCOUT TOPS:

Mississippi	2915
Kinderhook	3209
Maquoketa Shale	3362
Maquoketa Dolomito	3432

RECEIVED  
STATE CORPORATION COMMISSION

AUG 9 1953

CONSERVATION DIVISION  
Wichita, Kansas