

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Saline County, Sec. 2 Twp. 16 Rgs. 4 (E) W (W)

Location as "NE/CNWSW" or footage from lines C NE/4
Lease Owner Fender Pipe & Supply, Inc.
Lease Name Lockstrom Well No. 5
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 6-11-66 19____
Plugging completed 6-14-66 19____
Reason for abandonment of well or producing formation Depleted.

NORTH



Locate well correctly on above
Section Plot

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3436 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	345'	None
				5-1/2"	3433'	2814'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3436', sanded hole to 3400' and dumped 5 sacks of cement @ 3400' with dump bailer. Pulled 5 1/2' casing, set 10' rock bridge @ 250' and dumped 20 sacks of cement. Mudded hole to 30', set rock bridge and capped well with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
JUN 20 1966

PLUGGING COMPLETE.
KNIGHT CASING PULLING COMPANY

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (independent contractor) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 27th day of June, 1966

My commission expires May 20, 1968 Milton J. Volin Notary Public.

WELL LOG

15.169.60001.0000

DERBY OIL COMPANY
Lockstrom #5

C NE/4
Sec. 2, Twp. 16S, Rge. 4W
Saline County, Kansas

Total Depth: 3434 1/2'
Commenced: July 14, 1954
Completed: July 28, 1954
Drilled by Shields Drilling Co., Inc.

Elevation:
Treatment:
Production:

CASING RECORD

8 5/8" 345' Cmt'd w/ 250 sax
5 1/2" 3433 1/2' Cmt'd w/ 100 sax

-----Figures Indicate Bottom of Formation-----

Top Soil & Shale	35
Sand	45
Shale	330
Anhydrite	345
Anhydrite Lime	395
Broken Lime	435
Lime & Shale	985
Shale	1200
Shale, Shells, & Salt	1285
Shale & Shells	1435
Shale & Lime Streaks	1700
Shale	1780
Lime & Shale	2060
Shale	2225
Shale & Lime	2485
Lime & Shale	2840
Shale	2920
Shale & Lime	3027
Lime & Shale	3076
Lime	3116
Lime & Shale	3150
Shale	3172
Lime & Shale	3230
Shale	3432
Maquoketa Dolomite	3434 1/2 T.D.

RECEIVED
STATE CORPORATION COMMISSION
MAY 6 - 1966
CONSERVATION DIVISION
Wichita, Kansas

TOPS

Maquoketa Dolomite 3432'

Faint handwritten notes and bleed-through from the reverse side of the page.