

1060865

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,321-0000

SE NE NW, SEC. 36, T 19 S, R 29 W/E

4290 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Lease Name Truan "A" Well # 1

Operator: Chief Drilling Co., Inc.

County Lane 153.40

Name & Address 151 N. Main # 700

Well Total Depth 4720 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 334

Abandoned Oil Well Gas Well Input Well SWD Well D&A x

Other well as hereinafter indicated

Plugging Contractor Warrior Drilling Co. Rig # 2 License Number 5883

Address 905 Century Plaza, Wichita, KS 67202

Company to plug at: Hour: 1:45 am Day: 29 Month: July Year: 1986

Plugging proposal received from Marrion Burris

(company name) Warrior (phone) (316) 262-3791

Elevation 2819' GL

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2151-79'

1st plug at 2190' with 185 sx cement

2nd plug at 1100' with 70 sx cement

3rd plug at 360' with 40 sx cement

4th plug from 40' to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Paul Luthi

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 4:30 am Day: 29 Month: July Year: 1986

ACTUAL PLUGGING REPORT 1st plug at 2190' with 180 sx cement, 2nd plug at 1100' with

70 sx cement, 3rd plug at 360' with 40 sx cement, 4th plug from 40' to surface

with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug

to circulate mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix with 6% gel pumped by Allied.

(If additional description is necessary, use BACK of this form.)

7-31-86
JUL 31 1986

INVOICED

DATE JUL 31 1986

Signed Paul A. Luthi (TECHNICIAN)

INV. NO. 14584