

1060145

TO: STATE CORPORATION COMMISSION

1-27

API NUMBER 15-101-21,472 *0000
SE NW NW SEC. 26, T 19 S, R 29 W

CONSERVATION DIVISION - PLUGGING SECTION 4290 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 4290 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME JEWITT WELL # 1-D

TECHNICIAN'S PLUGGING REPORT

COUNTY LANE 152.43

OPERATOR LICENSE # 7775

WELL TOTAL DEPTH 4690 FEET

OPERATOR: WILTON PETROLEUM, INC

PRODUCTION CSG: SIZE 4 1/2" @ 4514' WITH 150 SX

NAME AND 901 KING AVE.

SURFACE CASING: SIZE 8 5/8" @ 291' WITH 170 SX

ADDRESS NYSSA, OR 97913

ABANDONED OIL WELL GAS WELL INPUT WELL D-26,520 INJ WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SWIFT SERVICES, INC LICENSE NUMBER 32382

ADDRESS PO BOX 466, NESS CITY, KS 67560

COMPANY TO PLUG AT: HOUR: 12:01 PM DAY: 27 MONTH: 01 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM TED FUCHS

(COMPANY NAME) SWIFT SERVICES, INC (PHONE) 785-798-2300

WERE: BOTTOM IS CEMENTED IN WITH PACKER.

PACKER IS CEMENTED IN- PRESSURED CASING TO 500# AND HELD FOR 15 MINUTES.

PERFORATED AT 1350'. PUMPED 150 SX CEMENT. MAXIMUM PRESSURE 850#. SHUT IN WITH 350#.

PUMPED 10 SX CEMENT DOWN BACKSIDE. PRESSURED TO 500# AND HELD.

PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 12:30 PM DAY: 27 MONTH: 01 YEAR: 1999

ACTUAL PLUGGING REPORT

PACKER IS CEMENTED IN- PRESSURE CASING TO 500# AND HELD FOR 15 MINUTES.

PERFORATED AT 1350'. PUMPED 150 SX MAXIMUM PRESSURE 850#. SHUT IN WITH 350#.

PUMPED 10 SX CEMENT DOWN BACKSIDE PRESSURED TO 500# AND HELD.

2-2-99

REMARKS: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, -USE BACK OF THIS FORM.)

I DID OBSERVE THIS PLUGGING.

SIGNED Michael J. Mauer (TECHNICIAN)

FORM CP-2/3

INVOICED

DATE 2-3-99

INV. NO. 60608