

1 050838

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,351 - 0000

E/2 E/2 NE, SEC. 34, T 19 S, R 29 W ~~X~~

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

3960 feet from (S) section line

Operator: Donald C. Slawson

330 feet from (E) section line

Name & Address 200 Douglas Bldg.

Lease Name Vsetecka "C" Well # 1

104 S. Broadway

County Lane 151.78

Wichita, KS 67202

Well Total Depth 4670' feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Plains Well Service License Number 4072

Address P.O. Box 346, No. 283 Hwy, Ness City, KS 67560

Company to plug at: Hour: 8:30 am Day: 31 Month: July Year: 19 86

Plugging proposal received from G. K. Thompson

(company name) Plains (phone) (913) 798-3995

were: 4 1/2" at 4669' Perfs at 4255-50'

- 1st plug sand back to 4200' and dump 4 sx cement on top of sand through bailer
- 2nd plug at 1400' built a bridge with a wooden plug and dumped 20' of sand on top of it. Then dumped 1 sack of Cal seal.
- 3rd plug at 800' squeezed 75 sx cement through hole ripped in 4 1/2" casing. Left 100' of cement in 4 1/2".
- 4th plug swabbed 4 1/2" casing down to 350' & filled it with cement
- 5th plug pumped 100 sx cement down 8 5/8" by 4 1/2" annulus.

Plugging Proposal Received by Don Ubel & Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:30 pm Day: 31 Month: July Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded bottom back to 4200' and dumped 4 sx cement on top of the sand through a bailer, 2nd plug at 1400' built a bridge with a wooden plug and dumped 20' of sand on top of it, then dumped 1 sack of Cal seal, 3rd plug at 800' squeezed 75 sx cement through hole ripped in 4 1/2" casing, left 100' of cement in 4 1/2" casing, 4th plug swabbed 4 1/2" casing down to 350' and filled it with cement, 5th plug pumped 100 sx cement down 8 5/8" by 4 1/2" annulus.

Maximum pressure 600 psi and shut in 100 psi on 8 5/8" by 4 1/2" annulus.

Remarks: Used 60/40 Pozmix with 6% gel 2% CaCl₂. No casing was recovered.
(If additional description is necessary, use BACK of this form.)

INVOICED (Stamp) Observe this plugging.

DATE AUG - 6 1986
INV. NO. 14628

AUG 5 1986
8-5-86

Signed Richard W Lacey
(TECHNICIAN)