

To: 1051645 5-4
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-20,5134/6001
NE NE NE, SEC. 22, T. 19 S, R. 29 W/EX

TECHNICIAN'S PLUGGING REPORT
Operator License # 30188
Operator: Royal Petroleum
Name & Address P.O. Box 1815
Liberal, KS 67905-1815

4950 feet from S section line
330 feet from E section line
Lease Name Mumma Well # 1
County Lane
Well Total Depth 4577 148.75 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 597

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547
Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 10 a.m. Day: 4 Month: 5 Year: 19 93

Plugging proposal received from Bob Sargent
(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 4 1/2" at 4576' w/140 sx cement, PBD 4544', Perfs at 4453-56, 4242-47'
DV tool at 2159' w/340 sx cement,
1st plug pump 300 lbs. hulls and fill to 4500' with cement,
2nd plug check backside.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 12:30 p.m. Day: 4 Month: 5 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug pumped 300 lbs. hulls and 250 sx cement down the 4 1/2" casing,
Maximum pressure 1000 and shut in 500 psi.

The 8 5/8" X 4 1/2" annulus was full. Checked visually.

RECEIVED
STATE CORPORATION COMMISSION
5-10-93
MAY 10 1993
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 65/35 Pozmix 8% gel by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED
observe this plugging.

DATE 5-17-93
INV. NO. 377-15
5-4

Signed Richard M. Lacey
TECHNICIAN