

1090201

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,998-0000

C NW NW SE SEC. 16 ; T 19 S, R 29 W/8
N SE Corner of W/8
2310 FSL feet from W/8 section line
SE Corner
2310 FEL feet from W/8 section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6113

Lease Name Kaczor Well # 1-16

Operator: Landmark Oil Exploration, Inc.
Name &
Address 105 South Broadway, Suite 1040
Wichita, KS 67202

County _____ Lane _____

Well Total Depth 4690 152.43 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 387 300

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor White & Ellis Drilling, Inc. License Number 5420

Address 401 East Douglas, Suite 500, Wichita, KS 67202

Company to plug at: Hour: 6:00 pm Day: 14 Month: July Year: 19 84

Plugging proposal received from Bob Kasper

(company name) White & Ellis - Great Bend (phone) 316-792-2424

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2160' with 50 sx cement

2nd plug at 1620' with 50 sx cement

3rd plug at 630' with 70 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement
Plugging Proposal Received by R. Barluttan
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 4:00 am Day: 15 Month: July Year: 1984

ACTUAL PLUGGING REPORT 1st plug at 2160' with 50 sx cement, 2nd plug at 1620' with

50 sx cement, 3rd plug at 630' with 70 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUL 18 1984

7-18-84

CONSERVATION DIVISION

Remarks: Used 60/40 Pozmix 2% gel 3% cc

(if additional description is necessary, use BACK of this for Wichita, Kansas)

INVOICED

DATE 7-27-84

WVZ NO. 2208

7-15

Signed R. Barluttan
(TECHNICIAN)