

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-20,885-0000

SFSWNW Sec. 17, T 19 S, R 29 W10

2310 feet from N1/4 section line

990 feet from W1/4 section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8725

Lease Name Hutchins Well # 5-17

Operator: Xplor Energy
Name & Address 1630 Welton Suite # 240
Denver, Colorado 80202

County Lane

Well Total Depth 4660 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 1/2" feet 258

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Big Springs Drilling Inc License Number 5381

Address Box 8287 - Mungen Station Wichita, Kans 67208

Company to plug at: Hour: 7:00 AM Day: 13 Month: 1 Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Dave Baise

(company name) Big Springs Drilling Inc. (phone)

were: 1st plug @ 2100' w/ 50 lbs cement

2nd plug @ 1300' w/ 50 lbs cement

3rd plug @ 310' w/ 50 lbs cement

4th plug @ 40-0' on solid bridge w/ 10 lbs cement

Circulated 15 lbs cement in rat hole. Run cementing pump cement

w/ 60/40 ppg w/ 2 1/2 gal + 3% ce

Signed Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:00 P.M. Day: 13 Month: 1 Year: 1984

ACTUAL PLUGGING REPORT

1st plug w/ hole full of heavy mud pumped 50 lbs cement through drill pipe @ 2100'. 2nd plug w/ hole full of heavy mud pumped 50 lbs cement through drill pipe to 1300'. 3rd plug w/ hole full of heavy mud pumped 50 lbs cement through drill pipe @ 310'. 4th plug filled hole to 40' w/ heavy mud dumped 1/2 lbs huller pushed rubber plug to 40' on solid bridge pumped 10 lbs cement through drill pipe to 40' filling hole to 0'.

Remarks: Circulated 15 lbs cement through drill pipe in rat hole.

I hereby certify that the above plugging instructions were given as herein stated and that I () did not) observe this plugging.

RECEIVED STATE CORPORATION COMMISSION 1-18-84 JAN 18 1984 CONSERVATION DIVISION Wichita, Kansas

INVOICED DATE 1-20-84 INV. NO. 9221 W

Signed Paul A. Luthi (TECHNICIAN)