

To: 1 080153
STATE CORPORATION COMMISSION 10-23
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License / 31645

Operator: JHS Energy Inc.

Name:

Address 1720 S. Belaire St., Ste. 1209

Denver, CO 80222-4304

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ O&A ☐

Other well as hereinafter indicated

Plugging Contractor D S & W Well Servicing License Number 6901

Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 12:30 p.m. Day: 23 Month: 10 Year: 19 97

Plugging proposal received from Bill Richardson

(company name) JHS Energy, Inc. (phone) 303-757-8811

were: 4 1/2" at 4719' w/175 sx cement, PBTD 4680', Perfs at 4190-4395', Casing leak approx. 1700'

1st plug sand back to 4140' and dump 4 sx cement on top of sand through bailer,

2nd plug run in and cut casing at 1330', pull up to 665', cut casing, pull 4 1/2" out, run in hole with 2 3/8" tubing to 1360', pump 80 sx cement,

3rd plug pull tubing up to 650', pump 50 sx cement, 4th plug pull tubing up to 290', pump 40 sx,

5th plug pull to 55' w/20 sx. Plugging Proposal Received by Kevin Strube (TECHNICIAN)

Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 2:30 p.m. Day: 23 Month: 10 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 4140' and dumped 4 sx cement on top of sand through bailer,

2nd plug ran in, cut casing at 1330', pulled up to 665', cut casing, pulled 4 1/2" casing out.

Ran in hole with 2 3/8" tubing to 1360' and pumped 80 sx cement,

3rd plug pulled tubing up to 650' and pumped 50 sx cement,

4th plug pulled up to 290' and pumped 40 sx cement, 5th plug pulled to 55' and pumped 20 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied. Recovered 665' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED (10/23/97) observe this plugging.

DATE OCT 29 1997

INV. NO. 49368

Signed Kevin Strube (TECHNICIAN)