

To: 1 080125 5-22 API NUMBER 15- Docket # D-19,464 101-20340-0007
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION App. S/2 S/2 SESEC. 14, T 19 S, R 29 W/E
130 S. Market, Room 2078
Wichita, KS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 31645

Operator: JHS Energy, Inc.

Name & Address 1720 S. Bellaire St., Ste. 1209

Denver, CO 80222

Lease Name Paris A Well # 2

County Lane 151.45

Well Total Depth 4660 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 259

Abandoned Oil Well Gas Well Input Well SMD Well X D&A

Other well as hereinafter indicated

Plugging Contractor D S & W Well Servicing License Number 6901

Address P.O. Box 231, Claflin, KS

Company to plug at: Hour: 1 p.m. Day: 22 Month: 5 Year: 19 97

Plugging proposal received from Bill Richardson

(company name) JHS Energy, Inc. (phone) 303-757-8811

Work: 4 1/2" at 4659' w/175 sx cement, PBTD 4659', Perfs at 4637-49', 4258-70'

1st plug run tubing to 3039' and pump 25 sx cement and 200 lbs. hulls,

2nd plug circulate cement from 1300' to surface.

Plugging Proposal Received by Kevin Strube
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1 p.m. Day: 22 Month: 5 Year: 19 97

ACTUAL PLUGGING REPORT Tubing parted in hole. Top of fish at 3039'. Well had 1" run between
8 5/8" X 4 1/2" to 1050' w/150 sx cement

May 22-pumped down 8 5/8" X 4 1/2" w/1/2 bbl. Pressured up to 500#.

1st plug pumped down 4 1/2" with 300 lbs. hulls and 260 sx cement.

Maximum pressure 500 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel 3% cc by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED
(If additional description is necessary, use BACK of this form.)

DATE JUN 06 1997

INV. NO. 48240

Signed Kevin D. Strube
(TECHNICIAN)