

To: 1 090116  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

9-21  
API NUMBER 15- 101-21,598-0000 135  
SE SW SW, SEC. 14, T 19 S, R 29 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 30033  
Operator: Graceland Oil Company  
Name & Address: P.O.Box 1068  
Hays, KS 67601

330 feet from S section line  
4290 feet from E section line  
Lease Name Paris Well # 1  
County Lane 151.77  
Well Total Depth 4670 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 305

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Emphasis Oil Operations License Number 8241  
Address P.O. Box 506, Russell, KS 67665

Company to plug at: Hour: 3:45 a.m. Day: 21 Month: 9 Year: 19 91

Plugging proposal received from Bill Owen

(company name) Emphasis Oil Operations (phone) 913-483-5345

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2167-98'  
1st plug at 2200' with 50 sx cement, 2nd plug at 1400' with 80 sx cement,  
3rd plug at 700' with 50 sx cement, 4th plug at 310' with 50 sx cement,  
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,  
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 7:30 a.m. Day: 21 Month: 9 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 2200' with 50 sx cement,  
2nd plug at 1400' with 80 sx cement,  
3rd plug at 700' with 50 sx cement,  
4th plug at 310' with 50 sx cement,  
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,  
7th plug to circulate mousehole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 25 1991  
9-25-91

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.

(If additional description is necessary, use BACK of this form.)

(XXXX did not) observe this plugging.

INVOICED  
DATE 10-4-91  
INV. NO. 33261

Signed [Signature]  
(TECHNICIAN)