

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-101-21785-00-00  
Spot: CSWSE Sec/Twnshp/Rge: 14-19S-29W  
730 feet from S Section Line, 1995 feet from E Section Line  
Lease/Unit Name: PARIS Well Number: 1  
County: LANE Total Vertical Depth: 4600 feet

Operator License No.: 32322  
Operator Name: DENIS F. ROBERTS  
Address: BOX 1252  
HAYS, KS 67601

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 209  
Production: Size \_\_\_\_\_ feet:  
Liner: Size \_\_\_\_\_ feet:

149.50

11/27

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/27/2000 12:00 AM  
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING  
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: 1ST PLUG AT 2194' WITH 50 SX CMT. 2ND PLUG AT 1370' WITH 80 SX CMT. 3RD PLUG AT 700' WITH 40 SX CMT. 4TH PLUG AT 250' WITH 40 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: Plugging Operations Were Not Witnessed  
Date/Time Plugging Completed: 11/27/2000 3:15 AM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:  
1ST PLUG AT 2194' WITH 50 SX CMT. 2ND PLUG AT 1370' WITH 80 SX CMT. 3RD PLUG AT 700' WITH 40 SX CMT. 4TH PLUG AT 250' WITH 40 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

RECEIVED  
KANSAS CORPORATION COMMISSION  
DEC 01 2000  
12-1-00  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

Signed  (TECHNICIAN) 

INVOICED  
DATE 12/1/00 NOV 29 2000  
INV. NO. 200106104910