

10-15

To: 1 051215
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,526-0000
C SE, SEC. 13, T 19 S, R 29 W/E
1320 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393
Operator: A.L. Abercrombie, Inc.
Name &
Address 150 North Main, Suite 801
Wichita, KS 67202

Lease Name Voshell Well # 3
County Lane 152.26
Well Total Depth 4685 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422
Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 10:45 a.m. Day: 15 Month: 10 Year: 19 89

Plugging proposal received from Wilmer Dreiling
(company name) Abercrombie Drilling, Inc. (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2141-70'
1st plug at 2170' with 50 sx cement, 2nd plug at 1200' with 80 sx cement,
3rd plug at 290' with 40 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 6:45 p.m. Day: 15 Month: 10 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 2170' with 50 sx cement,
2nd plug at 1200' with 80 sx cement,
3rd plug at 290' with 40 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 19 1989
10-19-89
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.
(If additional description is necessary, use BACK of this form.)

INVOICED
Please conserve this plugging.

DATE 10-24-89

Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 26187
10-15