

050585

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,386-~~000~~  
NE NW SW, SEC. 13, T 19 S, R 29 W/E

2310 feet from S section line  
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5364

Lease Name Voshell Well # 1

Operator: Beren Corporation  
Name & Address: 970 4th Financial Center  
Wichita, KS 67202

County Lane 150.38

Well Total Depth 4627 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 315

Abandoned Oil Well  Gas Well  Input Well  SMD Well  O&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 2:00 pm Day: 25 Month: July Year: 19 85

Plugging proposal received from Neil Peddicord

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 4626' PBTB 4532' Perfs at 4294-98', 4302-04', 4345-47', 4373-76'  
5 1/2 squeezed from 2100' to surface  
1st plug pump 1 sack hulls and 25 sx cement and 10 sx gel, 50 sx cement, 5 sx gel, and  
125 sx cement.

Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 3:30 pm Day: 25 Month: July Year: 19 85

ACTUAL PLUGGING REPORT Pumped 1 sack hulls, 25 sx cement, 10 sx gel, 50 sx cement, 5 sx gel and 125 sx cement. Cement fell and had to top off with Redi-Mix.

Remarks: No recovery. Used 60/40 Pozmix 6% gel & Redi-Mix by BJ-Titan.

INVOICED

DATE AUG 06 1985

INV. NO. 9321

STATE CORPORATION COMMISSION

RECEIVED  
AUG 2 1985  
8-2-85

Signed Richard W. Lacey  
(TECHNICIAN)

CONSERVATION DIVISION  
Wichita, Kansas