

To: 1080019  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-101-20,304-0001  
C SE NW, SEC. 15, T 19 S, R 29 W/E  
3300 feet from S section line  
3300 feet from E section line

3-6

TECHNICIAN'S PLUGGING REPORT  
Operator License # 4197  
Operator: Dunne Oil Company  
Name & Address: 100 S. Main, Ste. 410  
Wichita, KS 67202

Lease Name \*Broughton H Well # 1  
\*May be called Clark #1  
County Lane  
Well Total Depth 4695 152.58 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 286

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mike's Testing & Salvage Inc. License Number 31529  
Address: P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 3:50 p.m. Day: 6 Month: 3 Year: 19 96  
Plugging proposal received from Richard McIntyre

(company name) Mike's Testing & Salvage Inc. (phone) 316-938-2943  
w/c: 5 1/2" at 4694' w/175 sx cement, CIBP @ 4392'; Perfs at 4332-36, 4186-90'

- 1st plug sand back to 4136' and dump 5 sx cement on top of sand through bailer,
- 2nd plug pump 50 sx cement at 2100', 3rd plug pump 80 sx cement at 1300',
- 4th plug pump 40 sx cement at 600', 5th plug pump 40 sx cement at 300',
- 6th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Bill Johnson  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 6:30 p.m. Day: 6 Month: 3 Year: 1996

ACTUAL PLUGGING REPORT 1st plug pumped 20 sx common cement w/1 1/2% cc and 200 lbs shells,  
30 sx cement, wiper plug at 4100',  
2nd plug shot at 1300' and pumped 80 sx 60/40 Pozmix 6% gel cement,  
3rd plug casing loose at 800', pulled up to 600' and pumped 40 sx cement,  
4th plug pulled up to 300' and pumped 40 sx cement,  
5th plug circulated 40-0' with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 800' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

DATE MAR 26 1996 observe this plugging.

Signed Kevin P. Shults  
(TECHNICIAN)

INVOICED  
DATE \_\_\_\_\_  
INV. NO. 45131

RECEIVED  
MAR 23 A 10:38  
MANSAS CORP COM