

1050319

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 6668

Operator: Theodore I. Leben & Associates
Name & Address: 640 Broadway Plaza Building
Wichita, KS 67202

API NUMBER 15- 101-21,021-0000

E/2 NE SW, SEC. 35 ; T 19 S, R29 W/E
1980 65 N SE Corner of
feet from XXX section line
3630 65 W SE Corner of
feet from XXX section line

Lease Name Davis Well # 1-35County LaneWell Total Depth 4750 154.38 feetConductor Pipe: Size feetSurface Casing: Size 8 5/8 feet 344Abandoned Oil Well Gas Well Input Well SWD Well D&A XOther well as hereinafter indicated Plugging Contractor Abercrombie Drilling, Inc. License Number 5422Address 801 Union Center, Wichita, KS 67202Company to plug at: Hour: 4:00 am Day: 24 Month: August Year: 19 84Plugging proposal received from Dennis Johnson(company name) Abercrombie (phone) 316-262-1841were: to fill hole with heavy mud and spot cement through drill pipe1st plug at 2170' with 50 sx cement2nd plug at 1170' with 50 sx cement3rd plug at 420' with 50 sx cement
solid bridge4th plug hulls - plug at 40' -- cement to surface with 10 sx cement6th plug to circulate rat hole with 15 sx cementPlugging Proposal Received by Richard W. Lacey
(TECHNICIAN)Plugging Operations attended by Agent?: All Part None XOperations Completed: Hour: 7:45 pm Day: 24 Month: August Year: 19 84ACTUAL PLUGGING REPORT 1st plug at 2170' with 50 sx cement, 2nd plug at 1170' with 50sx cement, 3rd plug at 420' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with15 sx cement

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 9-7-84INV. NO. 3579

RECEIVED

STATE CORPORATION COMMISSION

Signed

Richard W. Lacey SD
(TECHNICIAN)

SEP 04 1984
9-4-84
CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84