

To: 1 060020 3-6
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 101-20,575 -0000

N/2 NW SE, SEC. 35, T 19 S, R 29 WEX
2310 feet from S section line
1950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4629
Operator: Brito Oil Company, Inc.
Name & Address: 120 S. Market, Ste. 300
Wichita, KS 67202

Lease Name McCoy J Well # 1
County Lane 152.75
Well Total Depth 4700 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 337

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage License Number 31529
Address P.O. Box 209, Chase, KS 67524-0209

Company to plug at: Hour: 9:30 a.m. Day: 6 Month: 3 Year: 1997

Plugging proposal received from Raul Brito
(company name) Brito Oil Company (phone) 316-263-8787

were: 4 1/2" at 4699' with 150 sx cement, Perfs at 4467-70, 4439-42, 4364-67, 4356-59'
1st plug at 2200' with 40 sx cement, 2nd plug at 1350' with 80 sx cement,
3rd plug at 700' with 40 sx cement, 4th plug at 360' with 50 sx cement,
5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Kevin Strube
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1 P.m. Day: 6 Month: 3 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 4200',
2nd plug at 2200' with 40 sx cement,
3rd plug at 1350' with 80 sx cement and 100 lbs. hulls,
4th plug at 700' with 40 sx cement,
5th plug at 360' with 50 sx cement,
6th plug at 40' with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1350' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I hereby agree to serve this plugging.

DATE MAR 11 1997
INV. NO. 47721
3-6

Signed Michael J. Morris
(TECHNICIAN)

RECEIVED
KANSAS CORP DIV
1997 MAR 10 P 3 50
3-10-97