

15169-00954-0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Saline County, Sec. 2 Twp. 16 Rge. 4 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE NE NE

Lease Owner Fender Pipe & Supply, Inc.

Lease Name Lockstrom Well No. 1

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_

Date well completed \_\_\_\_\_ 19\_\_

Application for plugging filed \_\_\_\_\_ 19\_\_

Application for plugging approved \_\_\_\_\_ 19\_\_

Plugging commenced 7-30-66 \_\_\_\_\_ 19\_\_

Plugging completed 8-4-66 \_\_\_\_\_ 19\_\_

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3442 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	339'	None
				4-1/2"	3438'	2927'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to 3438', sanded hole to 3424' and dumped 3 sacks of cement with dump bailer. Pulled 4 1/2 casing, set rock bridge from 260' to 250' and dumped 20 sacks of cement. Mudded hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 11 1966

CONSERVATION DIVISION  
WICHITA, KANSAS

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY

Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.

Noel J. Knight (employee of owner) or (owner or company) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight

Chase, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of August, 1966

Milton J. Volin

Notary Public.

My commission expires May 20, 1968

ROTARY DRILLERS' LOG

15-169-00954-0000

Derby Oil Company  
Box 1030  
Wichita, Kansas

Elevation 1322' KB

Lockstrom #1

8 5/8" x 4 1/2" Head  
6.60' below KB

C-NE NE NE  
Section 2-16s-4w  
Saline County, Kansas

Casing Record  
8 5/8" 339 KB cemented  
260 sacks cement circulated  
5 1/2" 3438 KB cemented 75  
sacks

Contractor: E. K. Carey, Contractor (Rig #2) McPherson, Kansas  
Geologist: Don Hollar, 422 West Douglass, Wichita, Kansas

Figures Indicate Bottom of Formations, K.S.

Rotary Base & Cellar	7
Clay and Shale	90
Shale & Shells	135
Shale & Shells	281
Sand	287
Lime	319
Cement	339
Lime & Shale	585
Lime & Shale	825
Lime & Shale	950
Shale & Shells	960
Shale & Shells	1320
Shale & Shells	1450
Lime & Shale	1600
Shale & Lime	1655
Lime & Shale	1735
Lime & Shale	1890
Lime & Shale	2015
Shale	2085
Shale & Lime	2190
Shale & Lime	2250
Shale	2290
Lime	2325
Lime	2440

Lime	2485
Lime	2580
Lime & Shale	2665
Lime & Shale	2740
Shale & Lime	2790
Shale & Shells	2870
Shale & Shells	2914
Lime	2955
Lime	2977
Lime	3028
Lime	3083
Lime	3120
Lime	3160
Lime	3184
Lime	3198
Shale	3210
Shale	3275
Shale	3305
Shale & Lime	3350
Shale	3361
Hounton Lime	3369
Shale	3390
Shale	3430
Shale	3438
Lime Maquoketa	3442

RECEIVED  
STATE GEOLOGICAL COMMISSION  
MAY 6 - 1966  
GEOLOGICAL COMMISSION  
Wichita, Kansas

The above Rotary Drillers Log is complete and correct to the best of my knowledge.

E. K. CAREY, CONTRACTOR

*Herbert Rhoton*

By Herbert Rhoton, Supt.