


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Saline County. Sec. 2 Twp. 16 Rge. 4 (E) W (W)
Location as "NE/CNW&SW&" or footage from lines SE SE NE
Lease Owner Fender Pipe & Supply, Inc.
Lease Name Lockstrom Well No. 4
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 6-20-66 19
Plugging completed 6-22-66 19
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott
Producing formation Depth to top Bottom Total Depth of Well 3431' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	330'	None
				5-1/2"	3430'	3897'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3431', sanded hole to 3420' and dumped 5 sacks of cement @ 3420' with dump bailer. Pulled 5 1/2" casing, set 10' rock bridge @ 250' and dumped 20 sacks of cement. Mudded hole to 30', set rock bridge and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

JUL 5 1966

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS
Conservation Division
Wichita, Kansas

STATE OF KANSAS COUNTY OF RICE ss.
Noel J. Knight (employee of owner) or of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
/Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of June, 19 66

My commission expires May 20, 1968 Notary Public.

Derby Oil Company
Box 1030
Wichita, Kansas

Elevation: K. B. 1317

8-5/8" x 5 1/2" Head 6.85'
below K. B.

Lockstrom #4

Casing Record:

SE SE NE
Sec. 2-16S-4W
Saline County, Kansas

8-5/8" 330' w/250 sacks

5 1/2" 3430' w/75 sacks,
set 1' off bottom

Well Commenced: 11-5-51

Well Completed: 11-18-51

Contractor: E. K. Carey, Contractor (Rig #1) Box 620, McPherson, Kansas
Geologist: Bob Douglass, Derby Geologist, Box 1030, Wichita, Kansas

Figures Indicate Bottom of Formation K. 3.

Base & cellar	8	Lime	2770
Shale & shells	200	Lime & shale	2800
Shale & lime shells	330	Lime & shale	2900
Shale & shells	355	Shale	2912
Shale & shells	400	Lime	2960
Lime & shale	525	Lime	2938
Lime & shale	750	Lime	3020
Lime & shale	955	Lime	3068
Lime & shale	1040	Lime	3112
Shale	1220	Lime	3130
Shale	1620	Lime	3156
Shale & lime	1305	Lime	3182
Lime & shale	1350	Lime	3190
Lime & shale	1935	Shale	3240
Lime & shale	2075	Shale	3335
Lime & shale	2095	Shale & lime	3400
Shale & lime	2235	Shale Maquoketa	3429
Shale & lime	2275	Maquoketa Dolomite	3431
Lime	2320		
Lime	2445		
Lime	2520		
Lime	2595		
Lime	2670		
Lime	2735		

RECEIVED
STATE CONSERVATION COMMISSION
MAY 6 - 1966
CONSERVATION DIVISION
WICHITA, KANSAS

Geologist Tops:

Mississippi	2910	(-1593)	Maquoketa Dolomite	3429	(-2112)
Kinderhook	3192	(-1375)	R. T. D.	3431	(-2114)
Hunton	3354	(-2037)	Set 5 1/2" @ 3430	or 1' off bottom	
Maquoketa Shale	3362	(-2045)			

The above Rotary Driller's Log is complete and correct to the best of my knowledge.

E. K. CAREY, CONTRACTOR
Herbert Rhoton
By Herbert Rhoton, Superintendent