

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Saline County. Sec. 2 Twp. 16 Rge. 4 (E) ~~E~~ (W)

Location as "NE/CNW/SW" or footage from lines W/2 W/2 SE/4 NE/4

Lease Owner Fender Pipe & Supply, Inc.

Lease Name Lockstrom Well No. 6

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19__

Application for plugging filed _____ 19__

Application for plugging approved _____ 19__


Plugging commenced 7-1-66 _____ 19__

Plugging completed 7-6-66 _____ 19__

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Flat

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3449 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	348'	None
				5-1/2"	3447'	2850'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3449', sanded hole to 3430' and dumped 5 sacks of cement @ 3430' with dump bailer. Pulled 5 1/2" casing, set rock bridge from 250' to 240' and dumped 20 sacks of cement. Mudded hole to 30', set rock bridge and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JUL 12 1966

CONSERVATION DIVISION

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of July, 19 66

My commission expires May 20, 1968

Milton J. Volin
Notary Public.

15-169-00624-0000

DRILLER'S LOG

Company: The Derby Oil Co.

W12
C/W/4 - NE/4 4
Sec: 2, Twn: 16, Rge: 14

Farm: Lockstrom Well No: 6
Total Depth: 3449

County: Saline, Kansas

Comm: 9/4/54 Comp: 9/23/54
Contractor: Peel Brothers, Inc.

Elevation:

Casing:
8 5/8" @ 348' Cem.
5 1/2" @ 3447' Cem.

Production:

Figures below indicate bottom of formation

Clay and shale	0'	40'
Shale		235
Shale and sand streaks		310
Shale		480
Broken lime and shale		1170
Shale		1820
Broken lime and shale		1970
Lime and shale		2465
Lime and chert		2480
Sandy lime and shale		2525
Lime and shale		2616
Pyriate and chert		2622
Lime and shale		2640
Lime and shale streaks		2700
Lime and shale		2775
Lime		2830
Lime and shale		3010
Lime		3045
Lime and chert		3230
Lime and shale		3375
Shale and lime streaks		3430
Lime and shale		3446
Dolomite		3449
Total depth		3449

RECEIVED
STATE CORPORATION COMMISSION
MAY 6 - 1966
CONSERVATION DIVISION
Wichita, Kansas

This is to certify that the above information to the best of my knowledge is true and correct.

PEEL BROTHERS, INC.

BY *H. S. Sutter*

SUBSCRIBED AND SWORN TO before me this 24 day of September

My commission expires September 28, 1957 *Norman S. Reese*
Notary Public