

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Saline County, Sec. 2 Twp. 16 Rge. 4 (E) W (W)

Location as "NE/CNW&SW&" or footage from lines S/2 S/2 NE/4
Lease Owner Fender Pipe & Supply, Inc.
Lease Name Lockstrom Well No. 8
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 6-15-66 _____ 19____
Plugging completed 6-18-66 _____ 19____
Reason for abandonment of well or producing formation Depleted

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3444 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	430'	None
				5-1/2"	3442'	2841'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3444', sanded hole to 3430' and dumped 5 sacks of cement @ 3430' with dump bailer. Pulled 5 1/2" casing, set rock bridge from 250' to 240' and dumped 20 sacks of cement. Mudded hole to 30', set rock bridge and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JUN 20 1966

06-20-66

PLUGGING COMPLETE.

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 27th day of June, 1966

My commission expires May 20, 1968

Milton J. Volin
Notary Public.

15-169-00626-0000

WELL LOG

Company: The Berby Oil Company

22-21-26/4

Farm: Lockstrom Well No: 8

Sec. 2, Twp: 16, Rge: 4

Total Depth: 3443'

County: Saline,
Kansas

Comm: 10-8-54 Comp: 10-17-54

Contractor: Seal Brothers, Inc.

Elevation:

Casing:

8 5/8"	0	430'	Con.
5 1/2"	0	3442'	Con.

Production:

Figures below indicate bottom of formation

Clay and shale	0'	62'
Sandy sand		66
Shale and shells		265
Shale and sand streaks		300
Shale and shells		435
Shale and Redbed		515
Shale and shells		630
Shale and lime streaks		840
Sand, shale and shells		1080
Lime streaks and shale		1575
Shale and lime		2995
Cherty lime and shale		3130
Lime and shale		3442
Dolomite		3443

RECEIVED
STATE CORPORATION COMMISSION

MAY 6 - 1966

CONSERVATION DIVISION
Wichita, Kansas

This is to certify that the above information is to the best of my knowledge true and correct.

SEAL BROTHERS, INC.

BY P. E. Sutton

Subscribed and sworn to before me this 20th day of

October

my commission expires September 26, 1967

Norma E. Reese
Notary Public