

LEASE NAME Rothe "B"

WELL NUMBER #1

SPOT LOCATION NE SE NW

SEC. 30 TWP J7S RGE J6 (E) or (W)

COUNTY Rush

Date Well Completed 9-10-75

Plugging Commenced 10-2-91

Plugging Completed 10-2-91

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR AFG Energy, Inc.

ADDRESS P.O. Box 605, Russell, KS 67665

PHONE # (913) 483-6213 OPERATORS LICENSE NO. 3456

Character of Well Gas  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing formation L-KC Depth to top 3470' bottom 3311' T.D. 3400'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD STATE CORPORATION COMMISSION

RECEIVED

OCT 08 1991

| Formation | Content     | From  | To    | Size   | Put in | Pulled |
|-----------|-------------|-------|-------|--------|--------|--------|
| L-KC      | Gas & Water | 3470' | 3311' | 8 5/8" | 237'   | None   |
|           |             |       |       | 4 1/2" | 3528'  |        |
|           |             |       |       |        |        |        |
|           |             |       |       |        |        |        |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Ran tubing to 3356-spotted 2 sxs. hulls. Pulled 6 jts. - 3170'. Spotted 60 sx. 60/40 Poz, 6% gel. Pulled 33 jts to 2250'. Spotted 60 sx. 60/40 Poz, 6% gel. Pulled 29 jts to 1250'. Circulated to surface w/60 sxs. 60/40 Poz, 6% gel. PULLED tubing. Filled 4 1/2" casing w/15 sx. of same. Hooked to 8 5/8" casing - 25 sx. 60/40 Poz, 6% gel. Pressured to 500#. SIP - 400#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. \_\_\_\_\_


Address Russell, KS 67665

STATE OF Kansas COUNTY OF Russell, ss.

Terry W. Piesker (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Terry W. Piesker

(Address) P.O. Box 605, Russell, KS



SUBSCRIBED AND SWORN TO before me this 7th day of October, 1991

Pamela K. Steckel  
Notary Public

My Commission expires: 11-19-92