


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Saline County, Sec. 17 Twp. 16S Rge. 1 (E) W (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines Center NE SE SW  
Lease Owner Deep Rock Oil Corporation  
Lease Name Louisa E. Heshner Well No. 1  
Office Address Box 1051, Tulsa, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well  
Date well completed June 28 19 46  
Application for plugging filed April 15 19 53  
Application for plugging approved April 16 19 53  
Plugging commenced June 18 19 53  
Plugging completed June 26 19 53  
Reason for abandonment of well or producing formation Oil Depleted



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production September 19 51

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Ruel Durkee

Producing formation Miss. Dolomite Depth to top 2688' Bottom 2700' Total Depth of Well 2700 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				10-3/4"	129'	None
				7"	2689'	1808'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Dumped in one ton of sand from 2700' to 2680'. Mixed and pumped in six sacks cement on top of sand and filled with mud to 135'. Set 20 sacks cement plug from 135' to 125'. Filled with mud from 125' to 15'. Mixed and pumped in five sacks cement and filled to top of hole and into cellar. Filled with dirt to ground level.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 23 1953

Name of Plugging Contractor R & S Pipe Pulling Company Wichita, Kansas  
Address Box 192, Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF RENO, ss.  
Jack Smith (employee of owner) or (owner) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Jack Smith*  
Box 1146, Hutchinson, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 22nd day of July, 19 53  
*Alice L Walker* Notary Public.

My commission expires September 28, 1955

PLUGGING  
FILE SEC 17 T 16 R 1W  
BOOK PAGE 93 LINE 32

Hesher #1

## Well Log - Rotary

0	30	Surface and Clay
35	55	Shale
55	150	Shale and Shells
150	240	Lime and Sand
240	270	Anhydrite
270	280	Lime and Sand
280	335	Lime
335	365	Red bed and Shale
365	1060	Lime and Shale
1060	1660	Shale
1660	1750	Shale and Shells
1750	1820	Lime
1820	1930	Shale
1930	2030	Lime and Shale
2030	2070	Shale
2070	2525	Lime
2525	2570	Shale
2570	2673	Shale and Shells
2673	2693	Shale
2693	2700	Grey Lime - little Chert
2700		Total Depth

RECEIVED  
STATE CORPORATION COMMISSION

APR 16 1953

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING

FILE SEC \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
BOOK PAGE \_\_\_\_\_ LINE \_\_\_\_\_