

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-169 - 00553.0001

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Melland Drilling Co, Inc.

Complete Address P.O. Box 892, McPherson, Kansas 67460

Lease Name Thomas Stein Well No. 1

Location Approx. NW NW SW Sec. 33 Twp. 16 Rge. 1 (East)(West)

County Saline Total Depth 2615'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Operator (Scott's Well Service) Halliburton Co.

Address _____ License No. _____

Operation Completed: Hour: 1:15 PM Day: 11 Month: August Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows: 5 1/2" - 2593' - ?

Ran tubing to 2615'. Pumped ^{w/ 2661 Halls} 49.5 bbl. gel through tubing at 2615' (49.5 bbl.)

Pumped 20 sacks cement (3 bbl.) through tubing at 2555' and displaced it with 10.5 bbl. gel (5.5 sacks gel). Pulled tubing to 190'.

Circulated cement to cellar - lay down tubing and filled hole to base of cellar (Total top plug 30 sacks cement)

Pumped 50 sacks cement into annulus.

No casing recovered.

Cement used 50/50 Permex w/ 20 gal and 38 cc.

Amount of Surface Casing: 8 3/8" - 133' - 100 sacks

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION

Signed: _____
Conservation Division Agent

INVOICED AUG 20 1982

DATE 8-30-82 CONSERVATION DIVISION
Wichita, Kansas

INV. NO. 973-W

RECEIVED
STATE OPERATIONS DIVISION
JUN 29 1982
CONSERVATION DIVISION
Wichita, Kansas

COMPANY: **W. S. Williams**
 CONTRACTOR: **Mallard Drilling Company**
 FARM: **Stein #1**
 LOCATION: **NW NW SW Sec. 33-16-1W
 Saline County, Kansas**
 COMMENCED: **February 9, 1953**
 COMPLETED: **February 16, 1953**

EL - 1279 KB

0	to	95	Sand and shale
95	to	133	Anhydrate
133	to	355	Lime
355	to	525	Lime
525	to	675	Lime and sand
675	to	835	Lime and sand
835	to	1590	Shale and lime
1590	to	1705	Lime
1705	to	1880	Lime
1880	to	1985	Lime and shale
1985	to	1996	Shale
1996	to	2060	Lime
2060	to	2270	Lime
2270	to	2495	Lime and shale
2495	to	2593	Shale
2593	to	2595	Mississippi
		2595	T. D. Rotary

Set 133 feet of 8 5/8" surface pipe. Cemented with 100 sacks cement.

Set 5 1/2" at 2593. Cemented with 50 sacks cement.

TOPS; 2593-- Mississippi

Measurements taken from derrick floor.

C E R T I F I C A T E

I, G. C. Nelson, do hereby certify that the above and foregoing is a true and correct copy of log of the Stein #1, Saline County, Kansas, as reflected by files of the Mallard Drilling Company.

G. C. Nelson

Subscribed and sworn to before me a Notary Public, within and for Sedgwick County, Kansas, this 12th day of March 1953.

Howard Wright

My commission expires 12/4/56



PERMIT TO
P.O. BOX 84737
DALLAS, TEXAS 75284

PAGE 1 OF 15769 00553-0001
FIELD TICKET
NO. 413841

DIRECT ANY CORRESPONDENCE TO
P.O. DRAWER 1431
BUNN, OKLAHOMA 7531

FORM 1905 R-7

WELL NO. AND FARM: 1 Stern
 COUNTY: Waller STATE: OK DATE: August 11, 62
 CHARGE TO: Welland Drilling Co. Inc. OWNER: Welland DUNEAN USE ONLY:
 ADDRESS: 1111 North Main CONTRACTOR: Welland LOCATION: Waller CODE: 50350
 CITY, STATE, ZIP: Waller, OK 7440 SHIPPED VIA: Truck LOCATION: 211 CODE: 50305
 DELIVERED TO: Location LOCATION: 3 CODE:
 ORDER NO.: BULK MATERIAL DELIVERY TICKET NO.: B-115
 WELL TYPE: CODE:
 TYPE AND PURPOSE OF JOB: Plug to Abandon
 TERMS: **NET** DUE BY THE 20TH OF FOLLOWING MONTH. INTEREST CHARGED AFTER 60 DAYS FROM DATE OF INVOICE.

PRICE REFERENCE	SECONDARY REF. OR PART NO.	CODE		DESCRIPTION	UNITS 1		UNITS 2		UNIT PRICE	AMOUNT
		L	D		QTY.	MEAS.	QTY.	MEAS.		
010-117				MILEAGE	3	hrs			2.10	6.30
010-910				Pump Charge			2	hrs	370	370.00
010-128				Extra hours	2	hrs			84.00	168.00
				Well	2	hrs			11.25	22.50
AS PER ATTACHED B TICKET NO. <u>115</u>										<u>114.77</u>

WAS JOB SATISFACTORILY COMPLETED? _____
 WAS OPERATION OF EQUIPMENT SATISFACTORY? _____
 WAS PERFORMANCE OF PERSONNEL SATISFACTORY? _____
 X _____ CUSTOMER OR HIS AGENT
 _____ HALLIBURTON OPERATOR
 TAX REFERENCES: _____
 SUB TOTAL: _____
 TAX: _____
 TAX: _____
 TOTAL: _____

RETAIN

HALL BURTON SERVICES
JOB LOG

WELL NO. 1 LEASE Men TICKET NO. 413841
 CUSTOMER M. Hand Drilling Co. Inc. PAGE NO. 1
 JOB TYPE PTA DATE Aug 11, 1982

FORM 2013 R-2

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	8:00							on location
	9:00							Gell up 60 bbl 2500s Gell
	9:30	3	52	1		100		Pump 52 bbl gell - 24's Halls - Tbz @ 2533
	10:15							Pull 24's - Tbz @ 2533
	10:30	3	6.8	1		700		mix 204's Cont. - 4.5 bbl Dipl 7 8.8 bbl Gell
	11:00	4	6.7 6.7			375		Pull Tbz to 170' mix 30 sks Cont. - 6.7 bbl
	1:00							Pull Tbz
	1:30	7	11.2	1		100		Hook up to Annulus incl mix Cont 30 sks 11.2 bbls

Thank you
Robert