

15169-00907-0001

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 6 1962
CONSERVATION DIVISION

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Saline

Location: SW-SW-SW- Sec. 33 Twp. 16 Rge. I (E) (W)

Name of Field: Hunter Total Depth: 2655'

I have this date completed supervision of plugging of:

Lease Name: Steinhor Well No. I-A

Operator's Full Name: F. S. Williams

Complete Address: 202 Malthy Bldg. McPherson, Kansas

Plugging Contractor R. D. Casing Pulling Co.

Address: Box 569 Ellinwood, Kansas License No. 236

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: Wash Down

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If Yes how long? _____ Reason: _____

Operation Completed: Hour 2:PM Day 29 Month 3 Year 62

The above well was plugged as follows:

Filled hole w/ sand from T.D. 2655' back to 2600' ran 5 sack cement w/ dump bailer.
Shot off and pulled 5 1/2" casing. Filled hole w/ mud from 2565' back to 180' set a 10'
rock bridge and ran 25 sack cement from 95' back to 30' set a bridge and ran 8 sack cement
from 25' back to zero 4' below ground level. 8 5/8" surface pipe 4' below ground level.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 4/12/62
INV. NO. 4806-W