

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

Form CP-3
Rev. 6-4-68

RECEIVED
STATE CORPORATION COMMISSION
DEC 23 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name George R. Hess & Sons

Complete Address 505 N. Charles, Mc Pherson, Kansas 67406

Lease Name Van Meter "B" Well No. 2

Location C S/2 NW SE Sec. 32 Twp. 16 Rge. 1 (E) (W) X

County Saline Total Depth 2659'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Flint Engineering & Construction Co.

Address 2375 W. Central, El Dorado, Kansas License No. 547

Operation Completed: Hour Noon Day 20 Month December Year 1969

The above well was plugged as follows:

Hole filled with sand to 2625' and cemented with 5 sacks cement.

Hole bailed to 160'. Rock bridge set from 160' to 150' and hole cemented with 30

sacks cement. Hole filled with mud to 40'. Rock bridge set from 40' to 30' and

hole cemented to base of cellar with 10 sacks cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 12/23/69
INV. NO. 1125-W