

15-101-20690-0000

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Lane SEC. 25 TWP. 19s RGE. 29w E/W  
 Location as in quarters or footage from lines:  
NE NW NW


Locate Well  
 correctly on above  
 Section Platt.

Lease Owner Donald C. Slawson  
 Lease Name Ware "C" #1 Well No. \_\_\_\_\_  
 Office Address 200 Douglas Bldg, Wichita, Ks. 67202  
 Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
 Date Well Completed \_\_\_\_\_  
 Application for plugging filed \_\_\_\_\_  
 Plugging commenced 11/3/82  
 Plugging completed 11/8/82  
 Reason for abandonment of well or producing formation \_\_\_\_\_

Depleted  
 Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4720'  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	364'	none
				4 1/2"	4719'	3233'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Moved in, plugged bottom with sand to 4250', ran 4 sacks cement, pulled 21" tension. Shot casing at 3615', 3400', & 3235', Pulled total of 78 joints. Plugged hole with 3 sacks hulls, 15 sacks gel, 70 sacks cement, 1 sack hulls, 15 sacks gel. Released plug & displaced with 100 sacks cement.

Plugging complete

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrel Kelso


(employee of owner) or (owner or operator) of the

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

R. Darrel Kelso  
 Box 347, Chase, Ks. 67524  
 (Address)

SUBSCRIBED AND SWORN TO before me this 12th day of November 1982



My Commission expires:

RECEIVED  
 Notary Public.  
 STATE CORPORATION COMMISSION

NOV 18 1982  
 11-18-82  
 CONSERVATION DIVISION  
 Wichita, Kansas