

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-101-21,440-0000

LEASE NAME Tennessee-Potter

WELL NUMBER 1-23

990 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 23 TWP. 19 RGE. 29 (W)

COUNTY Lane

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Landmark Oil & Texas El-Dorado

110 S. Main #510 550 W. Central #1108
 ADDRESS Wichita, Ks. 67202 Wichita, Ks. 67203

PHONE# (316) 265-8181 OPERATORS LICENSE NO. 06113 & 7245 Date Well Completed 11-25-87

Character of Well D&A Plugging Commenced 11-25-87

(Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging Completed 11-25-87

The plugging proposal was approved on 11-25-87 (date)

by Paul Luthi District #1 (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation NA Depth to Top NA Bottom NA T.D. 4655'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface	6 jts. 253' new	24# 8	5/8"	csg.	set @ 262'	w/160 sks 60/40 posmix 3% cc 2% gel

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Plugged w/210 sks 60/40 posmix 6% gel, 1st plug @ 2190' w/50 sks, 2nd plug @ 1400' w/80 sks, 3rd plug @ 290' w/50 sks, 10 sks @ 40', 10 sks RH, 10 sks MH, started @ 5:00 pm, Comp. @ 8:30 pm, Paul Luthi, Dist. #1

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Warrior Drilling Co. License No. 5883


Address 151 N. Main #700, Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

F. W. Shelton, Jr., (Employee of Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
F.W. Shelton, Jr.
 (Address) 151 N. Main #700

SUBSCRIBED AND SWORN TO before me this 1st day of Dec. 12-3-87 1987



Martha E. Gustin Notary Public
 Wichita, Kansas

NOTICE OF INTENTION TO DRILL

DRILL MUST BE SIGNED

(see rules on reverse side)

Starting Date November 14, 1987
month day year

API Number 15-101-21,440-00002

OPERATOR: License 06113, 7245
 Name Landmark Oil & Texas, El Dorado
 Address 110 S. Main, Suite 510
 City/State/Zip Wichita, KS 67202
 Contact Person Jeff Wood
 Phone 316/265-8181

Nw.. SE SE Sec 23... Twp. 19... S, Rg. 29... East
 990 Ft. from South Line of Section
 990 Ft. from East Line of Section
 (Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5883
 Name Warrior Drilling
 City/State Wichita, KS

Nearest lease or unit boundary line ... 990 feet
 County Lane
 Lease Name Tennessee-Potter Well # 1-23
 Ground surface elevation unknown feet MSL
 Domestic well within 330 feet: —yes X no
 Municipal well within one mile: —yes X no
 Depth to bottom of fresh water... 100
 Depth to bottom of usable water .. 1300
 Surface pipe by Alternate: 1 2 X
 Surface pipe planned to be set .. 250'
 Conductor pipe required no
 Projected Total Depth 4650 feet
 Formation Mississippi
 Title

Well Drilled For: Well Class: Type Equipment:
 Oil — SWD — Infield — Mud Rotary
 Gas — Inj — Pool Ext. — Air Rotary
 OWWO Expl Wildcat — Cable

If OWWO: old well info as follows:
 Operator
 Well Name
 Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
 Date 11-9-87 Signature of Operator or Agent [Signature] Title

For KCC Use:
 Conductor Pipe Required feet; Minimum Surface Pipe Required feet per Alt. (2)
 This Authorization Expires 5-13-88 Approved By R.H. 11-13-87

DATE: 11-18-87

Set 250
 Spud 11/17/87 -

NW SE SE Sec. 23 Twp. 19 S, Rg. 29 East
 X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ .40' to surface.....	feet depth with ... 10.....	sxs of 60-40. Ppz. mix, 6% CaCl, 3% gel
2nd plug @ .30' below surface.....	feet depth with ... 40.....	sxs of
3rd plug @ Base Cheyenne.....	feet depth with ... 80.....	sxs of
4th plug @ Base Anhydrite.....	feet depth with ... 50.....	sxs of
5th plug @	feet depth with	sxs of
(2) Rathole with 10.....	sxs	(b) Mousehole with .. 10..... sxs

NOTE: Agreement between operator and district office on plug placement and the amount of cement to be used is necessary prior to plugging.
 In Addition: Call district office after well is

PUSHER <u>Marion Burris</u>	TD <u>4655</u> FORMATION	SURFACE PIPE <u>8 3/8 @ 260'</u>	ANHYDRITE <u>2163</u> ELEVATION <u>2122</u>	STARTING TIME & DATE <u>5:30P</u>	COMPLETION TIME & DATE <u>8:20P 11-25</u>	1st PLUG @ <u>2190 FT. W/ 50 SX</u>	2nd PLUG @ <u>1400 FT. W/ 80 SX</u>	3rd PLUG @ <u>290 FT. W/ 50 SX</u>	4th PLUG @ <u>40-0 FT. W/ 10 SX</u>	RAT HOLE CIRCULATED W/ <u>10 SX</u>	MOUSE HOLE CIRCULATED W/ <u>10 SX</u>	WATER WELL PLUGGED W/ <u>10</u>	CEMENT COMPANY <u>Boj</u> <u>60/40 w/ 60</u>	TECHNICIAN <u>[Signature]</u>
-----------------------------	--------------------------	----------------------------------	---	-----------------------------------	---	-------------------------------------	-------------------------------------	------------------------------------	-------------------------------------	-------------------------------------	---------------------------------------	---------------------------------	--	-------------------------------

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 4 1987
 CONSERVATION DIVISION
 Wichita, Kansas
[Signature]