

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
30 South Market - Room 2078
Wichita, Ks. 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-21,724-0000
LEASE NAME McCOY "J"
WELL NUMBER 2-35

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

1320 Ft. from S Section Line
330 Ft. from E Section Line
SEC. 35 TWP. 19S RGE. 29 (E) or (W)

LEASE OPERATOR BRITO OIL COMPANY, INC.
ADDRESS 129 S. MARKET, SUITE 300, WICHITA, KS 67202

COUNTY LANE COUNTY, KS

PHONE# (316) 263-8787 OPERATORS LICENSE NO. 4629

Date Well Completed 7-09-96

Character of Well D/A

Plugging Commenced 7-09-96

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7-09-96

The plugging proposal was approved on 7-09-96 (date)

by STEVE PFEIFER (KCC District Agent's Name).

Is ACO-1 filed? Enclosed If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4702'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Fill with heavy mud. 1st plug from 2185'-1985'w/50 sks
2nd plug from 1100'- 780'w/80 sks
3rd plug from 600'- 400'w/50 sks
4th plug from 245'- 85'w/40 sks
5th plug from 40'- 0'w/10 sks, rathole 15 sks, total 245 sks.

Name of Plugging Contractor Abercrombie RTD, Inc. License No. 30684

Address 150 N. Main, Ste 801, Wichita, Ks. 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Brito Oil Company, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

(Employee of Operator) or (Operator)
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact
statements, and matters herein contained and the log of the above-described well as filed in
the same are true and correct, so help me God.

(Signature) Raul E. Brito, President
(Address) 120 S. Market, #300, Wichita, KS 67202



AND SWORN TO before me this 6th day of August, 19 96

Betty M. Abbott
Notary Public

My Commission Expires: 1-22-99

USE ONLY ONE SIDE OF EACH FORM

EFFECTIVE DATE: 6-30-96

State of Kansas
NOTICE OF INTENTION TO DRILL 101-21,724-0000

FORM MUST BE TYPED
FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

DISTRICT # 1
SEA? Yes No

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 7 4 1996
month day year

Spot E/2 E/2 SE Sec 35 Twp 19 S Rg 29W East West

OPERATOR: License # 4629
Name: Brito Oil Company, Inc.
Address: 120 S. Market, Suite 300
City/State/Zip: Wichita, KS 67202
Contact Person: Raul F. Brito
Phone: 316.263-8787

1320 FSL feet from South North line of Section
330 FEL feet from East West line of Section
IS SECTION X REGULAR IRREGULAR?

CONTRACTOR: License # 30684
Name: Abercrombie RTD, Inc.

(NOTE: Locate well on the Section Plat on Reverse Side)
County: Lane
Lease Name: McCoy "J" Well #: 2-35
Field Name: Paris South

Well Drilled For: Well Class: Type Equipment:
X Oil ... Enh Rec ... Infield X Mud Rotary
... Gas ... Storage X Pool Ext. ... Air Rotary
... GWWD ... Disposal ... Wildcat ... Cable
... Seismic: ... # of Holes ... Other
... Other

Is this a Prorated/Spaced Field? ... yes X no
Target Formation(s): Lans Marm Cherokee

If GWWD: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Nearest lease or unit boundary: 330'
Ground Surface Elevation: Est. 2823 feet MSL
Water well within one-quarter mile: ... yes X no

Directional, Deviated or Horizontal wellbore? ... yes X no
If yes, true vertical depth:
Bottom Hole Location:

Public water supply well within one mile: ... yes X no
Depth to bottom of fresh water: 180'
Depth to bottom of usable water: 1040'

Exp. 12/25/96

AFFIDAVIT

Surface Pipe by Alternate: 1 X 2
Length of Surface Pipe Planned to be set: 210'
Length of Conductor pipe required: none

Projected Total Depth: 4700'
Formation at Total Depth: Mississippi

Water Source for Drilling Operations:
... well ... farm pond X other

DWR Permit #: ...
Will Cores Be Taken? ... yes X no
If yes, proposed core:

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 22 1996

200' Alt. II Req.

CONSERVATION DIVISION
WICHITA, KS

Pusher [Signature]
SPUD DATE 7/3/96 INIT. [Signature]
LENGTH SURFACE PLANNED 210'
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 3/8 @ 217 CONDUCTOR
ANHYDRITE T- 2158 B- 2185 ELEVATION
TD 4700 FORMATION MISS
RAR PIPE @ DV TOOL ALT II DONE
SX Y N
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ Ft. W/ SX
1 Anhydrite Base @ 2185 Ft. W/ 50 SX
2 1/2 Base Anhy. @ 1100 Ft. W/ 80 SX
3 1/2, 1/2 Plug @ 600 Ft. W/ 50 SX
4 Bottom Surface @ 245 Ft. W/ 40 SX
5 40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX
WATER WELL SX (Irr. Well Pond
Hauling
TECHNICIAN SF DATE 7-9-96
TYPE OF CEMENT 60/40 p026 "sds" 1/4" FS
STARTING TIME 5:45 (AM/PM) DATE 7-9-96
COMPLETION TIME 7:45 (AM/PM) DATE 7-9-96
CEMENT COMPANY [Signature]