

**TYPE OR PRINT**  
**NOTICE: Fill out completely**  
**and return to Cons. Div.**  
**office within 30 days.**

LEASE NAME McCoy

WELL NUMBER J #1

           Ft. from S Section Line

           Ft. from E Section Line

SEC. 35 TWP. 19S RGE. 29W (E) or (W)

COUNTY Lane

Date Well Completed           

Plugging Commenced 3-5-97

Plugging Completed 3-6-97

LEASE OPERATOR Brito Oil Company, Inc.

ADDRESS 120 S. Market #300 Wichita, KS 67202

PHONE#(316) 263-8787 OPERATORS LICENSE NO. 4629

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on            (date)  
 by            (KCC District Agent's Name).

Is ACO-1 filed?            If not, is well log attached?           

Producing Formation            Depth to Top            Bottom            T.O. 4700'

Show depth and thickness of all water, oil and gas formations.

**OIL, GAS OR WATER RECORDS** | **CASING RECORD**

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	337'	none
				4 1/2	4699'	1350'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging material were used, state the character of same and depth placed, from            feet to            feet each sanded off bottom to 4200' & ran 4 sks cement. Shot pipe @ 2205', worked pipe Allied pumped 40 sks cement w/200# hulls at 2200'. Shot at 1350', worked pipe free. Pumped 80 sks cement w/100# hulls. Pulled to 700', pumped 40 sks cement. Pulled to 360', pumped 50 sks cement. Pulled to 40' & topped off w/10 sks. Pulled rest of csq. Plugging complete. 60/40 poz 6% gel.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 34229

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Brito Oil Company, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or Operator  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.


(Signature) *Mike Kelso*

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 18th day of March, 19 97

*Jane S. [Signature]*  
 Notary Public

My Commission Expires:           



RECEIVED  
 KANSAS CORP COM  
 1997 MAR 19 A 11:24  
 3-19-97