

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-20,718 -00-00

LEASE NAME Jennison

WELL NUMBER #2

4950 Ft. from (S) Section Line

3630 Ft. from (E) Section Line

SEC. 29 TWP. 16 RGE. 29 (X) or (W)

COUNTY Lane

Date Well Completed 10/29/82

Plugging Commenced 1:15 P.M. 11/13/01

Plugging Completed 12:45 P.M. 11/14/01

RECEIVED

NOV 21 2001

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR The Dane G. Hansen Trust

ADDRESS P. O. Box 187, Logan, Kansas 67646

PHONE#(785) 689-4816 OPERATORS LICENSE NO. 5285

Character of Well Oil

(Oil) Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on November 13, 2001 (date)

by Kevin Strube (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Kansas City Depth to Top 3842 Bottom 4468 T.D. 4516

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	326'	None
				5 1/2"	4514'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Pumped down 5 1/2' csg. 50 sx w/400# hulls, followed w/18 sx Gel. Started displacement. 40 Bbls. out on vacuum, took 69 bbls. total. Stopped, waited 30 min. pressure to 200#. Shut in w/100#. Next day - Pressured csg. to 1000#, held. Perf. at 1250'. Pumped 175 sx down 5 1/2" csg. Max pressure 1000#. Shut in 200#. Pumped 150 sx down backside. Max Pressure 200#. Shut in 50#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No. _____

Address P. O. Box 31, Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: The Dane G. Hansen Trust

STATE OF KANSAS COUNTY OF PHILLIPS, ss.

Richard L. Wallgren, Sr. (Employee of Operator) ~~and Operator~~ of above-described well, being first July sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
Richard L. Wallgren, Sr.
(Address) P. O. Box 187, Logan, Kansas

SUBSCRIBED AND SWORN TO before me this 19 day of November 2001



Betty Jane Bittel Notary Public

My Commission Expires: July 17, 2004