

29

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division,
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Ness County. Sec. 33 Twp. 17 Rge. 23 (E) W (W)
Location as "NE/CNWESW" or footage from lines C NW NE
Lease Owner Pickrell Drlg. Co.
Lease Name Anspaugh 'A' Well No. # 1
Office Address 705 4th Natl. Bank Bldg. ; Wichita, Ks. 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Sept. 25 1971
Application for plugging filed December 1 1971
Application for plugging approved December 2 1971
Plugging commenced December 23 1971
Plugging completed January 6 1972
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4389 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	233	None
				5 1/2"	4379	3010

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

December 23, 1971 Plugged off bottom. Dumped sand to 4350'. Mixed and dumped 5 sx of cement.
January 6, 1972 Plugged off top. Globe Oil Well Cementing Co. mixed and pumped down 8 5/8" surface casing, 2 sx hulls, 20 sx gel, 60 sx of cement and 5 sx gel. Released plug and 65 sx of cement.


RECEIVED
STATE CORPORATION COMMISSION
JAN 18 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor RUSS CASING PULLING, INC.
Address P. O. BOX 1082 ; GREAT BEND, KANSAS 67530

STATE OF Kansas COUNTY OF Sedgwick, ss.
Date M. Robinson (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Date M. Robinson
705 Fourth National Bank Bldg., Wichita, Kansas
(Address)



SUBSCRIBED AND SWORN to before me this 17th day of January, 1972
Esther Lamone
Notary Public.
My commission expires 20 January 19, 1973

ROTARY DRILLING LOG

15-135-20482-0000

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Building
Wichita, Kansas 67202

Rotary Drilling Commenced 9/15/71
Rotary Drilling Completed 9/25/71

LOCATION: Anspaugh "A" No. 1, C NW NE Sec. 33-17S-23W
Ness County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: Run 6 Jts. 8 5/8" surface casing set @ 233' K.B. Cemented with 140 sacks. Completed 6:30 P.M. September 15, 1971. Circulated.

Ran 133 Jts. 5 1/2" casing set @ 4379'. Cemented with 125 sacks common. Completed 7:00 A.M. September 25, 1971.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

40	Surface Soil		C.F.S.
905	Shale & Shells		3820
1095	Shale		3840
1300	Sand		3870
1639	Shale & Sand		3895
1678	Anhydrite		4070
2075	Shale		4165
2450	Shale & Lime		4180
2860	Lime & Shale		4300
3125	Shale & Lime Stringers		4365
3325	Lime & Shale		4383
3537	Shale & Lime		
3658	Shale & Sandy Lime		
3785	Shale & Lime		
4040	Lime & Shale	Board	S.L.M.
4142	Shale & Lime	Strap	4158.22
4165	Lime & Shale		4157.09
4230	Shale & Lime		1.13 Difference
4270	Lime & Shale		
4300	Ft. Scott		
4365	Lime & Sand		
4370	Ch. Sand		
4389	Mississippi, RTD		

RECEIVED
STATE CORPORATION COMMISSION
DEC 2 1971
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By [Signature]
C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 8th day of October, 1971, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: August 13, 1973

[Signature]
Ruth M. Sullivan Notary Public