

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-10-20343-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Lane _____ County. Sec. 32 Twp. 16S Rge. 29W E/W
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines _____
NW SW NW

Lease Owner Beren Corporation
Lease Name Dickey Well No. 1

Office Address 970 Fourth Financial Center, Wichita, KS
Character of Well (Completed as Oil, Gas or Dry Hole) _____

Dry Hole

Date Well completed Oct. 22 1978

Application for plugging filed (verbally) Oct. 22 1978

Application for plugging approved (verbally) Oct. 22 1978

Plugging commenced Oct. 22 1978

Plugging completed Oct. 22 1978

Reason for abandonment of well or producing formation _____

No commercial quantity of oil or gas encountered
If a producing well is abandoned, date of last production _____
19 _____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4581'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

T.D. 4581'

Set 1st plug at 1200' with 70 sacks

2nd plug at 250' with 20 sacks

3rd plug at 40' with 10 sacks

rathole with 5 sacks

Cemented with 50/50 posmix, 6% gel.

Plug was down at 6:30 a.m., 10-22-78.

State Plugger - Leo Massey.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of October, 1978



Sherrie L. Brooks
Sherrie L. Brooks Notary Public.

My commission expires August 21, 1982.

RECEIVED
STATE CORPORATION COMMISSION

NOV - 1 1978

CONSERVATION DIVISION
Wichita, Kansas

OPERATOR: Beren Corporation
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: Dickey #1
 LOCATION: NW SW NW, Section 32-16S-29W-
 Lane County, Kansas
 SPUD DATE: October 13, 1978
 COMPLETION DATE: October 22, 1978

0	280	Sand, Shale & Post Rock
280	1220	Sand & Shale
1220	2028	Sand & Shale
2028	2233	Sand, Shale & Red bed
2233	2265	Anhydrite
2265	2580	Shale & Shells
2580	2755	Shale & Shells
2755	2980	Shale & Lime
2980	3191	Shale & Lime
3191	3415	Shale & Lime
3415	3610	Shale & Lime
3610	3777	Shale & Lime
3777	3950	Lime & Shale
3950	4063	Lime & Shale
4063	4178	Lime & Shale
4178	4278	Shale & Lime
4278	4360	Shale & Lime
4360	4378	Shale & Lime
4378	4404	Lime
4404	4425	Lime
4425	4434	Shale & Lime
4434	4485	Lime
4485	4530	Lime
4530	4537	Lime
4537	4581	Lime
	4581	Rotary Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 NOV - 1 1978
 CONSERVATION DIVISION
 Wichita, Kansas

Spud hole at 6:45 p.m., October 13, 1978. Drilled 280' of 12 1/4" hole. Ran 6 joints of 8 5/8" - 28# casing. Set at 276.35' with 200 sacks of 60/40 posmix, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 12:00 midnite on October 13, 1978.

T.D. 4581'. Set 1st plug at 1200' with 70 sacks, 2nd plug at 250' with 20 sacks, 3rd plug at 40' with 10 sacks, rathole with 5 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 6:30 a.m. on October 22, 1978.

SAMPLE TOPS:

Anhydrite 2233'
 B/Anhydrite 2265'

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Dickey #1, NW SW NW, Section 32-16S-29W, Lane County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
 Jack L. Partridge,
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 30th day of October, 1978.

My commission expires 8-21-82.

Sherrie L. Brooks
 Sherrie Brooks, Notary Public