

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

15101-20871-0000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Lane SEC. 36 TWP. 16S RGE. 29W E/W
 Location as in quarters or footage from lines:
SE NW NE

		*	

Locate Well
 correctly on above
 Section Platt.

Lease Owner Mull Drilling Company Inc.
 Lease Name Fuller Well No. "B" #2
 Office Address P.O. Box 2758 Wichita, Ks. 67201
 Character of Well (Completed as Oil, Gas or Dry Hole): D.H.
 Date Well Completed 11-13-83
 Application for plugging filed 11-13-83
 Plugging commenced 11-13-83
 Plugging completed 11-13-83
 Reason for abandonment of well or producing formation _____

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Clyde Wiley

Producing formation _____ Depth to top _____ bottom T.D. 4630'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
surface	8 jts new	20#	8 5/8"	320' set @	323'	

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Plugged w/215 sx, 60-40 pos mix, 2% gel, 3% c.c.
 50 sx. @ 2190', 60 sx. @ 1410', 40 sx. @ 810'
 40 sx. @ 390', solid bridge plug @ 40', w/10 sx.
 15 sx. in the rat hole. Started @ 11:00 a.m. Completed
 @ 1:00 p.m. State Plugger Clyde Wiley

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Warrior Drilling Co., Rig #1

STATE OF Kansas COUNTY OF Sedgwick, ss.
F.W. SHELTON, JR., VICE PRES. (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) F.W. Shelton, Jr.
F.W. Shelton, Jr., Vice Pres.
 (Address)

905 Century Plaza Wichita, Ks.

SUBSCRIBED AND SWORN TO 14th day of November, 19 83



Martha E. Gustin
 Martha E. Gustin Notary Public.

My Commission expires: NOV 29 1983

Wichita, Kansas

DRILLERS LOG

November 14, 1983

15101-20871-0000

FULLER "B" #2
SE NW NE SEC. 36-16S-29W
LANE COUNTY, KANSAS

OPERATOR: Mull Drilling Company, Inc.
CONTRACTOR: Warrior Drilling Company
COMMENCED: Spudded in 11-05-83
COMPLETED: 11-13-83

8 jts. 8 5/8" set @ 323' w/190 sx.
60-40 pos mix.

0	85	Surface Clay
85	329	Sand & Clay
329	1500	Shale & Sand
1500	2209	Shale & Sand
2209	2239	Anhydrite
2239	3515	Shale
3515	4130	Shale & Lime
4130	4333	Lime & Shale
4333	4630	Lime
4630		RTD

Plugged w/215 sx. 60-40 posmix
2% gel, 3% c.c. 50 sx. @ 2190';
60 sx. @ 1410'; 40 sx. @ 810';
40 sx. @ 390'; solid bridge plug
@ 40' w/10 sx; 15 sx. in the rat
hole.

We certify that the above and foregoing is a true and correct copy
of the log on the Fuller "B" #2 located in Lane County, Kansas

WARRIOR DRILLING COMPANY

F.W. Shelton Jr.
F.W. SHELTON, JR., VICE PRES.

Subscribed and sworn to before me this 14th day of November, 1983.



Martha E. Gustin
Martha E. Gustin Notary Public