


15-101-2095-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Lane _____ County, Sec. 1 Twp. 17S Rge. (E) 29 (W)
Location as "NE/CNW/SW" or footage from lines NW NW SW
Lease Owner Chief Drilling Co., Inc.
Lease Name Terwilliger Well No. #3
Office Address 905 Century Plaza, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 5/21/78 19_____
Application for plugging filed 5/23/78 19_____
Application for plugging approved 5/21/78 19_____
Plugging commenced 5/21/78 19_____
Plugging completed 5/21/78 19_____
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production _____ 19_____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4548' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	294'	8 5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged through drill pipe @ 850' w/70 sx. cement
Plugged through drill pipe @ 240' w/20 sx. cement
Plugged through drill pipe @ 40' w/10 sx. cement

RECEIVED
STATE CORPORATION COMMISSION

MAY 24 1978

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Chief Drilling Co., Inc.
Address 905 Century Plaza, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Jim Robinson (employen of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Robinson
905 Century Plaza, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN to before me this 23rd day of May, 19 78

MARILYN SINARD
STATE NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
MY COMM. EXP. APR. 30, 1979

Marilyn Sinard
Marilyn Sinard
Notary Public.

commission expires _____

WELL LOG

CHIEF DRILLING CO., INC.
905 Century Plaza
Wichita, Kansas 67202

#3 TERWILLIGER
NW NW SW Sec. 1-17S-29W
Lane County, Kansas

CONTRACTOR: WARRIOR DRILLING, INC.
CASING RECORD: 8 5/8" @ 294' w/180 sx.

COMMENCED: May 12, 1978
COMPLETED: May 21, 1978

15-101-20315-0000

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATIONS</u>	
Surface Sand & Shale	0	330	2795 Gr.	
Shale	330	1412	2797 D.F.	
Sand & Shale	1412	2187	2800 K.B.	
Anhydrite	2188	2215		
Shale	2216	3680		
Shale & Lime	3680	4130		
Lime	4130	4176		
Shale & Lime	4176	4327		
Lime	4327	4548		
RTD	4548			

	<u>FORMATION TOPS</u>	
	Anhydrite	2187 + 613
	Base Anhydrite	2215 + 585
	Heebner	3934 - 1134
	Toronto	3952 - 1152
	Lansing	3968 - 1168
	BKC	4311 - 1511
	Marmaton	4320 - 1520
	Ft. Scott	4474 - 1674
	Cherokee	4500 - 1700
	RTD	4548 - 1748

D & A

RECEIVED
STATE CORPORATION COMMISSION
MAY 24 1978
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the NW NW SW of Sec. 1-17S-29W, Lane County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

Jim Robinson
Jim Robinson, Vice-President

Subscribed and sworn to before me this 23rd day of May, 1978.

Marilyn Sinaud
Marilyn Sinaud Notary Public