


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Lane \_\_\_\_\_ County, Sec. 2 Twp. 17S Rge. (E) 29 (W)  
Location as "NE/CNW/SW" or footage from lines C NW SE  
Lease Owner Chief Drilling Co., Inc. & Bill J. Porter  
Lease Name Gill Well No. #1  
Office Address 905 Century Plaza, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 1-23-77 19\_\_\_\_  
Application for plugging filed 1-23-77 19\_\_\_\_  
Application for plugging approved 1-23-77 19\_\_\_\_  
Plugging commenced 1-23-77 19\_\_\_\_  
Plugging completed 1-23-77 19\_\_\_\_  
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazar, Palco, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4620 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	280'	8 5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged through drill pipe @ 900' w/70 sx. cement  
Plugged through drill pipe @ 240' w/20 sx. "  
Plugged through drill pipe @ 40' w/10 sx. "

JAN 26 1977

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Chief Drilling Co., Inc.  
Address 905 Century Plaza, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Jim Robinson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Robinson  
905 Century Plaza, Wichita, Kansas 67202  
(Address)

Subscribed and sworn to before me this 25th day of January, 19 77

My commission expires \_\_\_\_\_

MARILYN SINARD  
STATE NOTARY PUBLIC  
SEDGWICK COUNTY, KANSAS  
MY COMM. EXP. APR. 30, 1979

Marilyn Sinard  
Marilyn Sinard  
Notary Public.

WELL LOG

15:101-202030000

CHIEF DRILLING CO., INC.  
905 Century Plaza  
Wichita, Kansas 67202

#1 GILL  
C NW SE Sec. 2-17S-29W  
Lane County, Kansas

CONTRACTOR: Company Tools  
CASING RECORD: 8 5/8" @ 280' w/185 sx.

COMMENCED: 1-10-77  
COMPLETED: 1-23-77

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATIONS</u>
Surface Clay	0	284	2794 Gr.
Shale	284	1596	2796 D.F.
Shale & Sand	1596	2185	2799 K.B.
Shale	2185	3815	
Shale & Lime	3815	3920	
Lime	3920	4620	
RTD	4620		

<u>ELECTRIC LOG TOPS:</u>	
Anhydrite	2192 + 607
Base Anhydrite	2219 + 580
Heebner	3927 - 1128
Toronto	3944 - 1145
Lansing	3964 - 1165
Base KC	4300 - 1501
Marmaton	4326 - 1527
Ft. Scott	4471 - 1672
Miss.	4586 - 1787
LTD	4620 - 1821

JAN 23 1977

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the C NW SE of Section 2-17S-29W, Lane County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

Jim Robinson  
Jim Robinson, Vice-President

Subscribed and sworn to before me this 25th day of January, 1977.

MARILYN SINARD  
STATE NOTARY PUBLIC  
SEDGWICK COUNTY, KANSAS  
MY COMM. EXP. APR. 31, 1978

Marilyn Sinard  
Marilyn Sinard Notary Public