

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-21,124 0000

LEASE NAME ZERENER

WELL NUMBER #1

SPOT LOCATION SW SW SE

SEC. 5 TWP. 19S RGE. 30W (E) or (W)

COUNTY LANE

Date Well Completed 2/8/85

Plugging Commenced 2/8/85

Plugging Completed 2/8/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR PINTO PETROLEUM

ADDRESS P.O. Box ¹¹¹⁸⁴ 18610, Wichita, Ks. ⁶⁷²¹¹ ~~67218~~

PHONE # (316) ~~883-8152~~ ²⁶³⁻⁴⁹⁶¹ OPERATORS LICENSE NO. 5232

Character of Well D/A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? 1

Is ACO-1 filed? No If not, is well log attached? Yes
(will be soon)

Producing formation D & A Depth to top _____ bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface				8 5/8	292'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set. btm plug @ 2200' w/50 sks; 1140' w/50 sks; 720' w/40 sks; hulls & plugs at 40' w/10sks; Rathole 10 sks; Mousehole 10 sks; 60-40 poz-mix w/2% gel, 3% CC by Allied

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied License No. Unknown
Address Great Bend, KS 67530

RECEIVED
STATE CORPORATION COMMISSION
3-20-85
MAR 20 1985

STATE OF Kansas COUNTY OF Sedgwick, ss.

~~Carl Nord~~ Bob Watchous (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Bob Watchous
(Address) Box 18610 Wichita 67218

KATHRYN L. FRERKING
NOTARY PUBLIC
STATE OF KANSAS
MY APPT. EXPIRES 8-21-85

SUBSCRIBED AND SWORN TO before me this 19th day of March, 1985

Kathryn L. Frerking
Notary Public

My Commission expires: August 21, 1985

WELL LOG

Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests
 tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static
 pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach
 copies needed. Attach copy of log.

Geological Survey

- Yes
- No
- Yes
- No
- Yes
- No

- Formation Description**
- Log
 - Sample

Name	Top	Bottom
sand/shale	0	295
shale	295	1715
sand/shale	1715	2785
lime/shale	2785	4100
Ks. City/Lime/shale	4100	4220
Lime/shale	4220	4310
KANSAS CITY	4310	4430
Marmaton/Ft. Scott	4430	4535
Lime/shale	4535	4650
Mississippi	4650	4690

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 20 1985
 CONSERVATION DIVISION
 Wichita, Kansas